

Handwritten initials

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-20027-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1969
CONSERVATION DIVISION
Wichita, Kansas

5-14-69

Operator's Full Name Mull Drilling Company, Incorporated.

Complete Address 1625 Wichita Plaza Building, Wichita, Kansas.

Lease Name Woerpel Well No. 3

Location CNW-SW Sec. 13 Twp. 5 Rge. (E) (W) 31

County Rawlins Total Depth 4206

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated.

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 2:00 PM Day 12 Month 5 Year 1969

The above well was plugged as follows:

216'--8 5/8" Surface casing, cement circulated with 150 Sx.

4205'--4 1/2" Production casing cemented on bottom with 125 Sx. Top perforations at 4041'.

Pushed plug to 4000' and built sand bridge then set 3 Sx. cement with dump bailer.

Pulled 4 1/2" casing and squeezed well with initially 5 sacks hulls and 1 sack gel and

followed with 100 Sx. cement from 1825' to 1500' then 32 sacks gel from 1500' to

220' and followed with 20 Sx. cement from 220' to 160' then 3 sacks gel from 220'

to 40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in

pressure--300#. Final shut-in pressure--75#. (Recovered 1841' 4 1/2" casing).

(Mudding and cementing by Allied)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 5/14/69
INV. NO. 9439-W