

M
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20019-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1969
CONSERVATION DIVISION
Wichita, Kansas
5-14-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mull Drilling Company, Incorporated.

Complete Address 1625 Wichita Plaza Building, Wichita, Kansas.

Lease Name Woerpel Well No. 2

Location CSE-SW Sec. 13 Twp. 5 Rge. (E) (W) 31

County Rawlins Total Depth 4370'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated.

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:15 PM Day 12 Month 5 Year 1969

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 150 Sx.
4369'--4 1/2" Production casing cemented on bottom with 125 Sx. No plug back indicated.
Top perforations from 4035' to 4037'.

Pushed plug to 4000', sanded back to 3975' and set 3 Sx. cement with dump bailer.

Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and 1 sack gel and followed with 100 Sx. cement from 1825' to 1500' then 32 sacks gel from 1500' to 220' and followed with 20 Sx. cement from 220' to 160' then 3 sacks gel from 160' to 40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure--300#. Final shut-in pressure--75#. (Recovered 1778' 4 1/2" casing).

(Mudding and cementing by Allied)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 5/14/69
INV. NO. 9738-W