

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-153-30177-00-00

RECEIVED  
STATE CORPORATION COMMISSION

NOV 23 1964  
11-23-64  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Sacred Heart Church Well No. 1

Location CNW-SW Sec. 36 Twp. 5 Rge. (E) (W) 33

County Rawlins Total Depth 4330

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 11:45AM Day 13 Month 11 Year 1964

The Above well was plugged as follows:

275'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 270', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. S. Nichols  
Well Plugging Supervisor

DATE 11/23/64

INV. NO. 200-W