

15-039-20018-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 8-6-67

LEASE NAME Feeley

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div. 39100
office within 30 days. 2310 1980

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 27 TWP. 5S RGE. 27 (E) or (W)

COUNTY Decatur

Date Well Completed 8-6-67

Plugging Commenced 5-12-87

Plugging Completed 5-12-87

LEASE OPERATOR Burch Exploration Inc.

ADDRESS 1190 Cambridge Court, Parker, CO 80134

PHONE# (303) 841-9417 OPERATORS LICENSE NO. 7448

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation Lansing K.C. Depth to Top 3647 Bottom 3847 T.D. 3854

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Shale		Surface	210	7		None
Lansing K.C.		Surface	3863	4 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Call state plugger, Carl Goodrow. Run wire line. Hole clean to 3830. Mix 300 lbs of hull w/first 20 sks of cement to plug perforations. Fill casing to surface w/140 sks of cement. Pressure to 300 lbs. Mix 40 sks pump down 7" casing. Pressure to 400 lbs. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Poe's Well Service License No. 6779


Address P.O. Box 115, Oberlin

STATE OF Kansas COUNTY OF Decatur, ss.

Melvin L. Taylor (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Melvin L. Taylor

(Address) 405 East 14th St., McCook, NE 69001



SUBSCRIBED AND SWORN TO before me this 22 day of May, 19 87

Larry L. Eisenmenger
Notary Public

My Commission Expires: _____
STATE CORPORATION COMMISSION

RECEIVED

5-26-87
MAY 2
CONSERVATION DIVISION
Wichita, Kansas