


15-039-20272-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Decatur County, Sec. 7 Twp. 5S Rge. 29 (X) (W)
Location as "NE/CNW/SW" or footage from lines c/E/2 - SE/4 NE/4
Lease Owner Indigo Oil Co.
Lease Name Anderson Well No. 1
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7/14/ 1973
Application for plugging filed verbal ~~XXXXXX~~ 7/15 1973
Application for plugging approved 7/15 1973
Plugging commenced 7/15 1973
Plugging completed 7/15 1973
Reason for abandonment of well or producing formation no commercial pay zones

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation none Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Sand	Water	0	175	8 5/8	212	-0-
All below surface	Water	175	TD			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with rotary mud

Displaced 110 cu. ft. @ 1600 ft. up to 1285 ft.

Displaced 30 cu. ft. @ 210 ft. up to 125 ft.

Pushed hull bridge to 30 ft. took weight of Kelly and pumped 10 cu. ft. filled back to surface.

All cement was 50-50 pozmix with 6% gel.

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1973
CONSERVATION DIVISION
Wichita, Kansas
17-24-73

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
Address Hill City, Kansas

STATE OF Nebraska, COUNTY OF Red Willow, ss.
George P. Stoepfelwerth, II, Agent (employee of owner) (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *George P. Stoepfelwerth*
2005 Norris, McCook, Nebraska
(Address)

SUBSCRIBED AND SWORN TO before me this 20 day of July, 19 73

My commission expires 3/24/73

J. McGinness
Notary Public

