


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Decatur County, Sec. 29 Twp. 5S Rge. 29W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner K & E DRILLING, INC.
Lease Name ANDERSON 'D' Well No. 2
Office Address 719 Union Center Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed November 3 19 60
Application for plugging filed November 4 19 60
Application for plugging approved November 4 19 60
Plugging commenced November 4 19 60
Plugging completed November 4 19 60
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4150 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	243'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

First plug w/1/2 sack hulls pushed to 400 and cemented w/20 sacks of cement through drill pipe
Second plug down 240' cemented through drill pipe w/20 sacks cement
Third plug down 40' cemented w/1/2 sack hulls & 9 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1960

CONSERVATION DIVISION
Wichita, Kansas

11-14-60

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
Dale Silcott
719 Union Center Bldg.,
(Address) Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 11th day of November, 19 60

My commission expires October 30, 1961
Wildalee Wind Notary Public.



15-039-00413-00-00

DRILLER'S WELL LOG

OPERATOR: K & E DRILLING, INC.
719 Union Center Bldg.
Wichita, Kansas

WELL NAME: #2 ANDERSON 'D'
LOCATION: C SW SW
Section 29-5S-29W
Decatur County, Kansas

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: October 28, 1960

CASING RECORD: 8 5/8" @ 243' w/200 sx

COMPLETED: November 3, 1960

ELEVATION: 2799 DF 2802 KB

ROTARY TOTAL DEPTH: 4150'

PRODUCTION: D & A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Surface soil and clay	60
Sand	125
Shale	1775
Shale and shells	2260
Shale, red bed	2555
Anhydrite	2585
Shale and shells	3190
Lime	3645
Lime and shale	3820
Lime	3920
Lime and chert	3995
Lime	4150 TD

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1960

CONSERVATION DIVISION
Wichita, Kansas

11-14-60

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, Dale Silcott of K&E DRILLING, INC., upon oath state
that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Dale Silcott
Dale Silcott

Subscribed and sworn to before me this 11th day of November, 19 60.

Wildalee Wind - Notary Public.

My Commission expires: October 30, 1961

