

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-19000-00-00
Spot: NWNWNWSE Sec/Twnshp/Rge: 12-29S-33W
2540 feet from S Section Line, 2540 feet from E Section Line
Lease Name: F MCCOY Well #: 1
County: HASKELL Total Vertical Depth: 2726 feet

Operator License No.: 32787
Op Name: KANSAS NATURAL GAS OPERATING, I
Address: PO BOX 818 1200 MAIN STREET
HAYS, KS 67601

PROD Size: 7 feet: 2720 WITH 900 SX CMT
SURF Size: 10.75 feet: 560 WITH 400 SX CMT

88⁶⁰

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/10/2005 8:30 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Revd. from: STEVE LEHNING Company: KANSAS NATURAL GAS Phone: (620) 675-8185

Proposed
Plugging
Method:

PUMP 400#HULLS WITH 30 SX CMT. MUD SPACER TO 700'. FILL 7" TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/10/2005 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 300# HULLS WITH 30 SX CMT FOR BOTTOM PLUG. MUD SPACER TO 700'.
PUMP 110 SX CMT FROM 700' TO SURFACE. PRESSURE TO 750 PSIG & SHUT IN.
RIG UP TO BACKSIDE. PRESSURED TO 400 PSIG IMMEDIATELY. BACKSIDE FULL.

Perfs:


Top	Bot	Thru	Comments
2682	2698		
2650	2658		

RECEIVED
JAN 21 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 1-21-05
INV. NO. 2005061092

Form CR-23