

3 022670

15-207-19460-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSAS FeeFundName & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE

Lic. #

6372Address: BOX 386, RR4, CHANUTE, KANSAS 66720Company to plug at: Hour: 9:00A.M. Day: _____ 14 Month: 12 2004Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300Were: THIS WAS AN OLD WELL ABOUT WHICH NOTHING IS KNOWN. THE PLUGGINGPROPOSAL WAS TO INSTALL SURFACE CASING, TO DRILL OUT THE WELL, AND TOCIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All _____

Part _____

TECHNICIAN

None _____

☒

Operations Completed: Hour:

12:00P.M.

Day: _____

14 Month: _____

12

2004

Actual Plugging Report:

SURFACE CASING WAS INSTALLED IN THE WELL AND THEWELL WAS DRILLED OUT TO 420'. AT THAT DEPTH IRON WAS ENCOUNTERED. 1" PIPE WASRAN INTO THE WELL TO 420'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENTCIRCULATED FRPM THE SURFACE CASING AT SURFACE. THE 1" WAS THEN REMOVED.DISPLACEMENT WAS FILLED FROM SURFACE. 197 SACKS OF CEMENT WERE PUMPEDINTO THIS WELL.Remarks: (GPS SESSION PT. NO. 71) (THIS WELL WAS WAS NOT SHOWN ON THE LEASE MAP.)(If additional description is necessary, use BACK of this form.)I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIANRECEIVED
DEC 22 2004
KCC WICHITA