

3 022676

15-207.19463-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20040041

SE,NE,SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.

1651 feet from south section line

2822 feet from east section line

TECHNICIAN'S PLUGGING REPORT

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 13 2005

Operator License #

101

Lease/Well#

APT NO. W37

County

WOODSON

Operator: STATE OF KANSAS

CONSERVATION DIVISION
WICHITA, KS

Well Total Depth 1000' feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 1000'

Address

Surface Casing: 8" Size Feet 20'

AB oil well Gas Well SWD Well/ Input Well

E-4207 D & A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE

Lic. #

6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 9:30A.M. Day: 28 Month: 12 2004

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 1000' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE

CASING.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

X

Part

TECHNICIAN

None

Operations Completed: Hour:

12:00P.M. Day:

28 Month:

12

2004

Actual Plugging Report:

3/4" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING

AT SURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8"

ANNULUS TO 575'. CEMENT WAS PUMPE INTO THE 1" PIPE UNTIL CEMENT CIRCULATED

FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT

WAS FILLED FROM SURFACE. 164 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO. 40) (THIS WELL WAS NO.W37 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I

DID

observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 13 2005
CONSERVATION DIVISION
WICHITA, KSClayton P. Titel
TECHNICIAN

B