

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20803-00-01
Spot: SESWSE Sec/Twnshp/Rge: 24-34S-35W
554 feet from S Section Line, 1874 feet from E Section Line
Lease Name: HUDKINS C Well #: 2
County: STEVENS Total Vertical Depth: 6658 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

CIBP Size: feet: 6200 WITH 2 SX CMT
CIBP Size: feet: 6400 WITH 2 SX CMT
COND Size: 20 feet: 40 WITH 4 YDS CMT
PROD Size: 5.52 feet: 6657 WITH 200 SX CMT
SURF Size: 8.625 feet: 1756 WITH 800 SX CMT

#216 39

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/10/2005 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: SET CIBP @ 6200' WITH 2 SX CMT. PLUG AT 1780' WITH 50 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: NONE
Date/Time Plugging Completed: 01/10/2005 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6386'. SET CIBP @ 6200' WITH 2 SX CMT ON TOP. 1ST PLUG RUN IN HOLE WITH TUBING TO 1780'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. 2ND PLUG PULL OUT OF HOLE WITH TUBING TO 650'. LOAD HOLE & PUMP 50 SX CMT. 3RD PLUG PULL OUT OF HOLE TO 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
6449	6455		
6429	6496		
6243	6252		
6227	6238		

RECEIVED
JAN 21 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2007' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed

Jim Holland (REGISTRATION)

INVOICE
DATE 1-21-05
INV. NO. 2005061095

Form CP-23