

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-01937-00-01
Spot: SWNESE Sec/Twnshp/Rge: 36-24S-15W
1650 feet from S Section Line, 990 feet from E Section Line
Lease Name: PRAEGER Well #: 4
County: STAFFORD Total Vertical Depth: 4782 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

L1 Size: 4.5 feet: 4774 50 SX CMT
PROD Size: 5.5 feet: 4590 WITH 200 SX CMT #15542
SURF Size: 8.625 feet: 279

Well Type: SWD UIC Docket No: D24988.0 Date/Time to Plug: 01/07/2005 3:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4760' & 5 SX CMT. RUN TUBING TO 960'. CIRCULATE CASING WITH 150 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/07/2005 4:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4777'. 5 1/2" X 8 5/8" ANNULUS HAD 200 SX HALLIBURTON LITE CEMENT PUMPED DOWN IT. ESTIMATED CASING BOTTOM OF CMT IS 1500'. SANDED TO 4760' & 5 SX CMT WITH BAILER. RUN TUBING IN TO 960'. CIRCULATED 5 1/2" CASING WITH 150 SX CMT. LAID DOWN TUBING. HOLE STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
4730	4748		

RECEIVED
JAN 21 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Stephen J. Gafer
(TECHNICIAN)

INVOICED
DATE 1-21-05
INV. NO. 2005061097

Form CP-2/3