

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-21444-00-00  
Spot: SESENW Sec/Twnshp/Rge: 9-16S-13W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: DEUTSCH Well #: 6  
County: BARTON Total Vertical Depth: 3379 feet

Operator License No.: 30380  
Op Name: HUPFER OPERATING, INC.  
Address: PO BOX 216  
HAYS, KS 67601

PROD Size: 4.5 feet: 3376 UNKNOWN  
SURF Size: 8.625 feet: 359 190 SX CMT

#10982

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/19/2005 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: DENNIS D HUPFER Company: HUPFER OPERATING, INC. Phone: (785) 628-8666

Proposed Plugging Method: Ordered 185 sxs 60/40 pozmix - 10% gel - 500# hulls. (Brought 240 sxs).  
Dakota 221' - 471'. Anhy. 874' - 894'. Salt 1284' - 1574'.

Plugging Proposal Received By: PAT STAAB  
Date/Time Plugging Completed: 01/19/2005 4:00 PM

WitnessType: COMPLETE (100%)  
KCC Agent: PAT STAAB

Actual Plugging Report:

Mike's Testing sanded off bottom to 3300' and topped with 4 sxs cement using a sand pump.  
RIH and cut casing at 2205' - pulled casing to 1600'.  
Swift rigged to casing and pumped 75 sxs 60/40 pozmix with 300# hulls.  
Pulled casing to 925' - pumped 40 sxs cement with 100# hulls mixed in.  
Pulled casing to 500' - pumped 20 sxs cement with 100# hulls mixed in.  
Pulled casing to 150' - pumped 35 sxs cement to circulate cement to surface.  
POOH. Pulled rest of casing. Hole standing full.  
Used 170 sxs cement and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3376	3379		

RECEIVED  
JAN 24 2005  
KCC WICHITA

Remarks: SWIFT CEMENTING SERVICES, INC.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

JAN 20 2005

INVOICED  
DATE 1-24-05  
INV. NO. 2005061101

AL TIPTON  
BOX 157, HAYS, KS. 67601

#6 DEUTSCH

9-16-13W  
SE SE NW

CONTR ALLEN DRLG. CO.

CTY BARTON

GEOLOGICAL J. C. MUSGROVE

FIELD TRAPP

E 1921 KB CM 8/12/78 <sup>CARD</sup> ISSUED 9/14/78 IP P 50 BOPD + 50 BWPD  
ARB 3376-79

+	+	+
+	•	+
+	+	+

API 15-009-21,444

SMP	TOPS	DEPTH	DATUM
*ANH	874	+1047	
HEEB	3045	-1124	
TOR	3064	-1143	
DOUG	3082	-1161	
LANS	3129	-1208	
BKC	3327	-1406	
ARB	3373	-1452	
RTD	3379	-1458	
*DRILLERS TOP			

8-5/8" 359/190sx, 4 1/2" 3376  
DST (1) 3356-3379/45-30-45-30, 180'  
GIP, 480'GO, 180'MO, SIP 1081-  
1060#, FP 61-183#, 204-265#  
MICT - CO TD, AC 500

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

W.A. 11/13  
W.A. 11/13  
W.A. 11/13