

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10257-00-01
Spot: SWNE Sec/Twnshp/Rge: 6-35S-41W
1995 feet from N Section Line, 1980 feet from E Section Line
Lease Name: FULKERSON B Well #: 1
County: MORTON Total Vertical Depth: 5390 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

PROD Size: 4.5 feet: 3454 WITH 250 SX CMT \$ 175.18
SURF Size: 8.625 feet: 1482 WITH 650 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/14/2005 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Revd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 20 SX CMT. PLUG AT 1500' WITH 50 SX CMT. PLUG AT 350' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/17/2005 11:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 700# HULLS & 40 SX CMT TO PLUG BOTTOM. DISPLACE WITH MUD. PRESSURE TO 500 PSIG & SHUT IN. 1ST PLUG PULL OUT OF HOLE TO 1500'. LOAD HOLE WITH MUD & PUMP 45 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL PUT OF HOLE WITH CASING TO 350'. SDON. 1/17/05; LOAD HOLE & PUMP 30 SX CMT. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3096	3261		
3052	3056		
2926	2930		
2880	2884		

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 24 2005
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1520' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland (TECHNICIAN) PERFIT

INVOICED
DATE 1-24-05
NO. 2005061103

Form CR-23