

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-023-20185-: 00-01 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR MAREXCO OPERATORS LICENSE NO. 9152

ADDRESS P.O. Box 706, Edmond, Oklahoma 73034 PHONE # (405) 340-6387

LEASE (FARM) McKee WELL NO. 34-36 WELL LOCATION SW-SE COUNTY Cheyenne

SEC. 36 TWP. 5S RGE. 37 (E) or (W) TOTAL DEPTH 4660 PLUG BACK TD 4639

Check One:

OIL WELL _____ GAS WELL _____ D & A xx SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 367 CEMENTED WITH xxxxxxx SACKS

CASING SIZE 4 1/2 SET AT 4660 CEMENTED WITH 125 SACKS

PERFORATED AT 4480-84; 4443-46; 4338-4342

CONDITION OF WELL: GOOD xxxxx POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL CIBP @ 4476 w/ lsk cem, pump 25sx 60/40
poz, 6% gel w/ lsk hulls and displace to 4071 w/ mud, shoot off csg @ 2500 and
pump 60sx same cem to +2150, pump 40sx same cem to 400, and 10 sx 40'-0'
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO OWWO IS ACO-1 FILED? yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 8:00 AM 1-28-88

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Steve Marden PHONE # (405) 340-6387

ADDRESS P.O. Box 706, Edmond, OK 73034

PLUGGING CONTRACTOR ALLIED Cementing Co. LICENSE NO. _____

ADDRESS Ness City, KS PHONE # (913) 798-3843

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
(Operator or Agent)

DATE: 2/9/88