

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

RECEIVED  
STATE CORPORATION COMMISSION

SEP 27 1978  
9-27-78  
CONSERVATION DIVISION  
Wichita, Kansas

API Number 15 - 023 -20,077-00-00 (of this well)  
Lease Owner A. L. Abercrombie, Inc.  
Address 801 Union Center, Wichita, Kansas 67202  
Lease (Farm Name) Fisher Well No. 4  
Well Location C W/2 SW NE Sec. 35 Twp. 5S Rge. (X) 37 (W)  
County Cheyenne Total Depth 4905' Field Name \_\_\_\_\_  
Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ Rotary D & A X  
Well Log attached with this application as required Yes  
Date and hour plugging is desired to begin September 21, 1978, 4:30 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Gerrell Veatch Address 38 Walnut Drive, Hill City, Ks. 67642  
Plugging Contractor Abercrombie Drilling, Inc. License No. \_\_\_\_\_  
Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Abercrombie Drilling, Inc.  
Address 801 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge  
Applicant or Acting Agent  
Jack L. Partridge, Ass't. Sec.-Treas.  
Date: September 26, 1978

**IMPORTANT**  
 Kans. Geo. Survey request  
 samples on this well.


**KANSAS DRILLERS LOG**

S. 35 T. 5 R. 37 W

Loc. W2 SW NE

County Cheyenne

640 Acres  
N



Locate well correctly

Elev.: Gr. 3320'

DF 3323' KB 3325'

API No. 15 — 023 — 20,077-00-00  
 County Number

Operator  
A. L. Abercrombie, Inc.

Address  
801 Union Center Wichita, Kansas 67202

Well No. #4 Lease Name  
Fisher

Footage Location  
 feet from (N) (S) line feet from (E) (W) line

Principal Contractor Abercrombie Drilling, Inc. Geologist Vic Reiserer

Spud Date September 8, 1978 Total Depth 4905' P.B.T.D. -----

Date Completed September 21, 1978 Oil Purchaser -----

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8-5/8"	28#	396 KB	60-40 posmix	275	3% CaCl 2% gel

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 27 1978  
 9-27-78  
 CONSERVATION DIVISION  
 Wichita, Kansas

**INITIAL PRODUCTION**

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

15-023-20077-00-00

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Dry Hole

Operator  
A. L. Abercrombie, Inc.

Well No. 4 Lease Name Fisher

S 35 T 5S R 37 W

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST#1 (4500-4535) 30", 45", 60", 45". Strong blow. Recovered 2340' sw. IFP 272-757, IBHP 1044, FFP 778-1002, FBHP 1044.			SAMPLE TOPS:	
			Anhydrite	3104 (+ 311)
			B/Anhydrite	3052 (+ 273)
			Queen Hill	4045 (- 720)
			Heebner	4140 (- 815)
			Toronto	4179 (- 854)
			Lansing	4196 (- 871)
			B/KC	4475 (-1150)
			Marmaton	4490 (-1165)
			Pawnee	4569 (-1244)
DST#2 (4556-4590) 30", 45", 60", 45". Recovered 1900' sw. IFP 531-858, IBHP 858, FFP 858-858, FBHP 858.				
DST#3 (4698-4725) 30", 30", 30", 30". Weak blow. Recovered 20' mud. IFP 20-20, KBHP 20, FFP 20-20, FBHP 20.				
Clay & sand	0	340	ELECTRIC LOG TOPS:	
Shale	340	397	Anhydrite	3008 (+ 317)
Sand & shale	397	1008	Heebner	4134 (- 809)
Shale & sand	1008	2480	Lansing	4194 (- 869)
Lime	2480	2500	Marmaton	4481 (-1156)
Shale & lime	2990	3014	Pawnee	4569 (-1244)
Anhydrite	3014	3054	Mississippian	4880 (-1555)
Shale & lime	3054	3114		
Lime & shale	3114	3321	LTD	4906 (-1581)
Shale & lime	3321	3395		
Lime & shale	3395	4200	RTD	4905 (-1580)
Lime	4200	4780		
Lime & shale	4780	4880		
Lime	4880	4905		
Rotary Total Depth		4905		

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 27 1978  
9-27-78  
CONSERVATION DIVISION  
Wichita, Kansas

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p><i>Jack L. Partridge</i> Signature</p> <p>Jack L. Partridge, Ass't. Secretary-Treasurer Title</p> <p>September 26, 1978 Date</p>
---------------	---

State of Kansas



15-023-20077-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

September 26, 1978

WELL PLUGGING AUTHORITY

Well No.	4
Lease	Fisher
Description	W/2 SW NE Sec. 35-5-37W
County	Cheyenne
Total Depth	4905
Plugging Contractor	Co. Tools


A. L. Abercrombie, Inc.  
801 Union Center  
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. Leo Massey, 109 West 15th, Hays, Kansas 67601  
is hereby assigned to supervise the plugging of the above named well.