

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION
APR 12 1978
4-12-78
CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - 023 - 20,063-0000 (of this well)
Lease Owner Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202
Lease (Farm Name) Fisher "B" Well No. 1
Well Location C SE SE Sec. 27 Twp. 5S Rge. (E) 37 (W)
County Cheyenne Total Depth 4900' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin April 6, 1978, 8:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Darrel Stevens Address 1323 E. Warren, Wakeeney, Ks. 67672

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent
Jack L. Partridge, Ass't. Sec.-Treas.

Date: April 10, 1978

IMPORTANT
Kans. Geo. Survey request samples on this well.

KANSAS DRILLERS LOG


S. 27 T. 5 R. 37 ^K/_W

API No. 15 — 023 — 20,063 ⁻⁰⁰⁻⁰⁰
County Number

Loc. SE SE

County Cheyenne

640 Acres
N



Locate well correctly

Elev.: Gr. 3262

DF 3265 KB 3267

Operator
Abercrombie Drilling, Inc.

Address
801 Union Center Wichita, Kansas 67202

Well No. #1 Lease Name Fisher "B"

Footage Location
feet from (N) (S) line _____ feet from (E) (W) line _____

Principal Contractor Abercrombie Drilling, Inc. Geologist _____

Spud Date March 28, 1978 Total Depth 4900' P.B.T.D. _____

Date Completed April 6, 1978 Oil Purchaser _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	28#	366'	Common	275	2% gel 3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

15-023-20063-00-00

Operator: Abercrombie Drilling, Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole

Well No. 1 Lease Name Fisher "B"

S 27 T 5 R 37 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface clay & sand	0	320	SAMPLE TOPS:	
Shale	320	370	Anhydrite	2964 (+ 303)
Sand & shale	370	2659	B/Anhydrite	3000 (+ 267)
Shale & Anhydrite stringers	2659	2780	Heebner	4092 (- 825)
Shale	2780	2917	Toronto	4129 (- 862)
Shale & lime	2917	3144	Lansing	4145 (- 878)
Shale & lime	3144	4302	Stark Shale	4346 (-1079)
Lime	4302	4341	B/KC	4404 (-1137)
Shale & lime	4341	4535	Marmaton	4440 (-1173)
Lime	4535	4670	Cher. Shale	4577 (-1310)
Shale & lime	4670	4791	Cher. Sand	4660 (-1393)
Lime	4791	4900		
Rotary Total Depth		4900		
DST#1 (4259-4341) 30", 45", 60", 45". Strong blow. Rec. 1350' mw. IFP 61-377, IBHP 1344, FFP 387-622, FBHP 1323. Temp. 144.				
DST#2 (4363-4405) 30", 45", 30", 45". Weak blow - 30" died. Rec. 20' mud. IFP 30-30, IBHP 1253, FFP 30-30, FBHP 1151. Temp. 114.				
DST#3 (4516-4550) 30", 45", 30", 45". Rec. 5' mud. IFP 20-20, IBHP 30, FFP 20-20, FBHP 20.				
ELECTRIC LOG TOPS				
Anhydrite 2966 (+ 301)				
B/Anhydrite 3002 (+ 265)				
Heebner 4089 (- 822)				
Toronto 4129 (- 862)				
Lansing 4146 (- 879)				
B/KC 4404 (-1137)				
Marmaton 4440 (-1173)				
Cherokee 4581 (-1314)				
Cher. Sand 4659 (-1392)				
Miss. 4838 (-1571)				
ELTD 4902 (-1635)				
RTD 4900 (-1633)				

RECEIVED
APR 12 1978

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received: _____
 Signature: Jack L. Partridge
 Title: Ass't. Secretary-Treasurer
 Date: April 10, 1978

State of Kansas



15-023-20063-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

April 18, 1978

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Fisher "B"
Description	SE SE Sec. 27-5-37W
County	Cheyenne
Total Depth	4900
Plugging Contractor	Abercrombie Drilling, Inc.


Abercrombie Drilling, Inc.
801 Union Center
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above named well.