

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20329-00-00
Spot: CNWNWSE Sec/Twnshp/Rge: 6-5S-36W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: COOPER GUY L Well Number: 2
County: RAWLINS Total Vertical Depth: 4776 feet

Operator License No.: 4273 Conductor Pipe: Size feet: 155.22
Op Name: H & R EXPLORATION & PRODUCTION, I Surface Casing: Size 8.625 feet: 364 w/280 sxs cmt
Address: 1113 SOUTH 10TH AVENUE PO BOX 101 Production: Size 4.5 feet: 1298 w/150 sxs cmt
SIDNEY, NE 69162 Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/14/2002 9:00 AM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: RANDY Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 160 cu.ft. cement slurry.

Plugging Proposal Received By: CARL GOODROW
Date/Time Plugging Completed: 01/14/2002 11:00 AM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 364' w/280 sxs cwc. 4 1/2" set at 1298' w/150 sxs.
Prod.Perfs 1170' - 1184'.
Exempt area. PBTD 1298'.
The hole had no gas and no fluid.
Shot off and recovered 900' of casing.
Filled hole with 160 cu.ft. of cement slurry.
Plug complete.

RECEIVED
JAN 31 2002
KCC WICHITA

Remarks:

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE Feb 1-02

INV. NO. 2002061328

JAN 23 2002

SHAKESPEARE OIL COMPANY, INC.
 P.O. BOX 669, SALEM, ILL.

#2 GUY L. COOPER

6-5-36W
 NW NW SE

CONTR MURFIN DRILLING CO. CTY RAWLINS

GEOL FIELD LITTLE BEAVER CREEK SE

3381 KB CM 6/17/78 CARD ISSUED 8/3/78 IF 100,000 CFGPD

NIOB 1170-84
 NEW PAY

+	+	+
+	+	+
+	+	+

API 15-153-20,329

LOG	TOPS	DEPTH	DATUM
NIOB	1164	+2217	
ANH	3110	+ 277	
B ANH	3148	+ 233	
TOP	4112	- 731	
DREAD	4210	- 829	
HEEB	4228	- 847	
LKC	4276	- 895	
BKC	4570	-1189	
MARM	4656	-1275	
CHER SH	4706	-1325	
BTD	4775	-1394	
LTD	4776	-1395	

8-5/8" 364/280sx, 4 1/2" 1298/150sx
 DST (1) 4452-70/45-45-45-45, 85' DM,
 10' M, w/OIL SP, SIP 1221-1156#,
 FP 74-82#, 82-82#
 DST (2) 4648-68/30-30-30-30, 10' DM,
 SIP 41-25#, FP 16-16#, 16-16#
 MICT - PF 1/1170-84 (NIOB), FRAC
 30,000GA 80%FOAM + 26,500# SD,

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS