

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20308-00-00  
Spot: CSWSWSE Sec/Twnshp/Rge: 6-5S-36W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: COOPER GUY L Well Number: 1  
County: RAWLINS Total Vertical Depth: 5016 feet

Operator License No.: 4273 Conductor Pipe: Size feet: \$163.02  
Op Name: H & R EXPLORATION & PRODUCTION, I Surface Casing: Size 8.625 feet: 325 w/250 sxs cmt  
Address: 1113 SOUTH 10TH AVENUE PO BOX 101 Production: Size 4.5 feet: 4600 w/200 sxs cmt  
SIDNEY, NE 69162 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/14/2002 12:00 PM  
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.  
Proposal Rcvd. from: RANDY Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 460 cu.ft. cement slurry.  
Order permanent plug.  
Order 4 sxs common cement.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 01/14/2002 2:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 325' w/250 sxs cwc. 4 1/2" set at 4600' w/200 sxs.  
Prod. Perfs 4456' - 4462'.  
Exempt area. PBTD 4600'.  
Fluid level near TD. Depleted zone.  
Set permanent plug at 4400' with 4 sxs common cement on plug with bailer.  
Shot off and recovered 2000' of casing.  
Filled hole with 460 cu.ft. of cement slurry.  
Plug complete.

RECEIVED  
JAN 31 2002  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE Feb 1-02

WIZ. NO. 2002061328

JAN 23 2002

SHAKESPEARE OIL CO., INC.  
P.O. BOX 669, SALEM, ILL.

#1 GUY L. COOPER

6-5-36W  
SW SW SE

CONTR MURFIN DRLG. CO.

CTY RAWLINS

GEOL

FIELD WC (2 SE OF ABD LITTLE

E 3382 KB CM 1/25/78 CARD ISSUED 3/9/78 IP

BEAVER CREEK)  
P 150 BOPD, 1% W  
LANS 4456-62

+	+	+
+	+	+
+	+	+

API 15-153-20,308

LOG	TOPS	DEPTH	DATUM
NI OB		1169	+2213
FT HAYS		1594	+1788
B FT HAYS		1646	+1736
ANH		3113	+ 269
B ANH		3153	+ 229
HEEB		4223	- 841
LANS		4272	- 890
CHER SH		4698	-1316
MISS		4918	-1536
RTD		5010	-1628
LTD		5016	-1634

8-5/8" 325/250sx, 4 1/2" 4600/200sx  
DST (1) 4217-80/45-45-45, 525' WCM  
SIP 1276-1158#, FP 229-298#  
DST (2) 4424-69/30-45-30-45, 114' Ho&  
GCM, 124' MGO, 1116' GO, SIP 1181-  
1158#, FP 91-527#  
DST (3) 4518-70/30-30-30-30, 20' M,  
SIP 217-114#, FP 57-57#  
MICT - SWB DWN, PF 4456-62, ON/FU  
2850', SWB 28 BO, AC 1500, SWB & REC  
LD, SWB 20 BO/2 HRS, SION, FL 2700'  
FROM SURF, SWB 55 BO/2 1/2 HRS, SWB 120  
BO, POP, P 81 BO/18 HRS, P 166 BO/  
26 HRS

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS