

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20319-00-00  
Spot: CSENESW Sec/Twnshp/Rge: 6-5S-36W  
1650 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: GENEVA JENKS Well Number: 1  
County: RAWLINS Total Vertical Depth: 4580 feet

Operator License No.: 4273 Conductor Pipe: Size feet: 8 1/48.85  
Op Name: H & R EXPLORATION & PRODUCTION, I Surface Casing: Size 8.625 feet: 380 w/275 sxs cmt  
Address: 1113 SOUTH 10TH AVENUE PO BOX 101 Production: Size 4.5 feet: 4570 w/200 sxs cmt  
SIDNEY, NE 69162 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/15/2002 8:00 AM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: RANDY Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 460 cu.ft. cement slurry.  
Order one permanent plug.  
Order 4 sxs common cement.

Plugging Proposal Received By: CARL GOODROW  
Date/Time Plugging Completed: 01/15/2002 9:00 AM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 380' w/275 sxs cwc. 4 1/2" set at 4570' w/200 sxs.  
Prod. Perfs 4462' - 4468'.  
Exempt area. PBSD 4570'.  
Fluid level near TD. Depleted zone.  
Set permanent plug at 4400' with 4 sxs common cement on plug with bailer.  
Shot off and recovered 1100' of 4 1/2" casing.  
Filled hole with 460 cu.ft. of cement slurry.  
Plug complete.

Remarks:

Plugged through: CSG

KCC

RECEIVED

FEB 13 2002

KCC WICHITA

JAN 28 2002

Signed

Carl Goodrow

FEB 11 2002

(TECHNICIAN)

HAYS, KS

INVOICED

Form CP-2/3

DATE

Feb 15 02

INV. NO.

2002061385

SHAKESPEARE OIL CO., INC.  
BOX 669, SALEM, ILL.

#1 GENEVA JENKS

6-5-36W  
SE NE SW

CONTR MURFIN DRLG. CO.

CTY RAWLINS

GEOL DARRELL ROBERTS

FIELD LITTLE BEAVER CREEK SE CONF.

E 3394 KB CM 5/31/78 CARD ISSUED 6/29/78 IP P 20 BOPD, N/W  
LKC 4462-68

	+	+
	+	+

API 15-153-20,319

LOG	TOPS	DEPTH	DATUM
ANH		3124	+ 270
B ANH		3160	+ 234
TOP		4116	- 722
OREAD		4212	- 818
HEEB		4230	- 836
LANS		4281	- 887
J J ZN		4464	-1070
B J ZN		4470	-1076
LTD		4578	-1184
RTD		4580	-1186

8-5/8" 380/275sx, 4 1/2" 4570/200sx  
DST (1) 4426-72/45-45-45, 400' GIP,  
455' CGO, 160' OCM, SIP 1145-1097#  
FP 40-174#, 182-245#  
MICT - PF 4462-68, AC 500, RE-AC  
3000, 15%, REC LD, SWB 3 1/2 BOPH, N/W  
T&R, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS