

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20338-00-01  
Spot: SWSE Sec/Twnshp/Rge: 31-5S-36W  
660 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: BRINEY B Well Number: 2  
County: RAWLINS Total Vertical Depth: 4730 feet

Operator License No.: 6600  
Op Name: KARST, DON WELL SERVICE, INC.  
Address: PO BOX 863  
RUSSELL, KS 67665

Production Casing Size: 4.5 feet: 4729 w/150 sxs cmt  
Surface Casing Size: 8.625 feet: 418 w/300 sxs cmt

#153 73

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/23/2003 9:30 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: JIM CLARK Company: CLAR-MAR OIL COMPANY Phone: (785) 625-3863

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Plug through casing.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/23/2003 10:40 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforations 4420' - 4674'. TD 4680'. PBTD 4646'. Junk in hole at 2750'.  
8 5/8" surface casing set at 418' w/300 sxs cement.  
4 1/2" production casing set at 4729' w/150 sxs cement.  
Connected to 4 1/2" production casing - pumped 265 sxs cement with 500# hulls.  
Max. P.S.I. 600#. S.I.P. 0#.  
Connected to 8 5/8" surface casing - pumped 1/4 sack cement.  
Max. P.S.I. 300#. S.I.P. 300#.

RECEIVED  
OCT 02 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04



Signed Darrel Dipman  
(TECHNICIAN)

INVOICED  
DATE 10-2-03  
INV. NO. 2004060563

Form CP-2/3

SEP 24 2003

THUNDERBIRD DRILLING, INC. #2 BRINEY "B" 31-5-36W  
 P. O. BOX 18407 WICHITA, KS. 67218 C SW SE  
 CONTR THUNDERBIRD DRILLING CTY RAWLINS

GEOL \_\_\_\_\_ FIELD TOVREA  
 E 3421 KB<sub>CM</sub> 11/11/78 CARD ISSUED 12/7/78 IP P 120 BOPD  
 MARM 4608-74 OA

+	+	+
+	+	+
+	+	+

API 15-153-20,338

LOG TOPS	DEPTH	DATUM
ANH	3102	+ 319
B ANH	3136	+ 285
HEEB	4230	- 809
TOR	4268	- 847
LANS	4290	- 869
B KC	4565	-1144
MARM	4578	-1157
PAW	4662	-1241
LTD	4729	-1308
RTD	4730	-1309

8-5/8" 418/300, 4-1/2" 4729/150 SX  
 DST (1) 4405-34/45-45-45-45, 300' CL O,  
 280' MO, SIP 1263-1228#, FP 52-225#  
 DST (2) 4598-4620/45-45-45-45, 1740' CL  
 O, 120' MO, SIP 830-822#, FP 199-  
 657#  
 DST (3) 4618-40/45-45-45-45, 2055' CL O,  
 120' MO, SIP 1099-1099#, FP 182-  
 865#  
 DST (4) 4665-85/45-45-45-45, 2480' CL  
 GSY O, 120' MO, SIP 951-951#, FP  
 536-951#  
 MICT - CO, PF 4664-74, SWB 51 BOPH, RP  
 4650, PF 4626-32, 4608-14, SWB 34 BOPH,  
 NAT, PULL PLUG, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

DON KARST WELL SVC 31-05S-06W  
 HAYS KS 67601 C SW SE

#2 BRINEY B OWWO

site 14-1/2 S & 1 W OF MCDONALD KS city: RAWLINS API 15-153-20338-A  
 contr: POE SERVICING field: TOVREA  
 gsc: NONE  
 date 05/24/95 spd date 06/01/95 drlg comp 06/24/95 card issued 10/16/95 last revised 10/16/95


ELV: 3421 KB, 3416 GL LOG	depth/datum
ANH	3102 +319
B/ANH	3136 +285
HEEB	4230 -809
TOR	4268 -847
LANS	4290 -869
BKC	4565 -1144
MARM	4578 -1157
PAW	4662 -1241
PBTD	4680 -1259
LTD OLD	4729 -1308
RTD OLD	4730 -1309

IP Status  
 OIL P 40 BO & 8 BWP, LKC 4420-4555 OA, 07/25/95.  
 OLD INFO: OPERATOR WAS THUNDERBIRD  
 DRILLING, 2 BRINEY B; SPD 11/11/78, 11/21/78 8-5/8"  
 418/300 SX (ALT 1); 4-1/2" 4729/150 SX, OIL, P 120  
 BOPD, NW, MARM 4608-4674 OA, 12/01/78 (CARD  
 ISSUED 12/07/78)  
 CONTR: THUNDERBIRD DRILLING  
 NO CORES  
 DST (1) 4405-4434 (LKC), / 45-45-45-45, REC 300' CLEAN  
 OIL, 280' MDY OIL ISIP 1263# FSIP 1228# IFP 52#  
 FFP 225#

DON KARST WELL SVC 31-05S-36W  
 HAYS KS 67601 C SW SE

#2 BRINEY B OWWO

DST (2) 4598-4620 (MARM), / 45-45-45-45, REC 1740' CLEAN OIL, 120' MDY OIL ISIP 830#  
 FSIP 822# IFP 199#, FFP 657#  
 DST (3) 4618-4640 (MARM), / 45-45-45-45, REC 2055' CLEAN OIL, 120' MDY OIL ISIP 1099#  
 FSIP 1099# IFP 182# FFP 865#  
 DST (4) 4665-4685 (PAW), / 45-45-45-45, REC 2480' CLEAN GSY OIL, 120' MDY OIL ISIP 951#  
 FSIP 951# IFP 536# FFP 951#  
 MICT - CO, PF (PAW) 4664-4674, SWB 51 BOPH, SET BP AT 4650, PF (PAW) 4626-4632, 4608-4614,  
 SWB 34 BOPH, NAT, PULL PLUG, POP, P 120 BOPD, NW, 12/1/78  
 NEW INFO: FR 05/24/95, RE-ENTERED 06/01/95 WSH DWN, SD.WEA, RESUMED, WSHG DWN  
 TO 4730, DC 06/24/95 CSG: PROD CSG ALREADY IN HOLE  
 COMMENT: KCC API 15-153-20338-0001  
 TRGT ZN: KC, PAW, MARM; PTD 4700 (MARM), DELAYED COMP 6/14/95, MICT - CO, SET  
 CIBP AT 4646, PF (LKC) 4552-4555, W / 2 SPF, AC 1000 GAL (15% INS), SO, PF (LKC) 4533-4536,  
 W / 2 SPF, AC 500 GAL (15% INS), SO, PF (LKC) 4473-4477, W / 2 SPF, AC 750 GAL (15% NE),  
 SO, PF (LKC) 4464-4466, W / 2 SPF, AC 250 GAL (15% INS), SO, PF (LKC) 4420-4424, W / 2 SPF,  
 AC 1250 GAL (15% DSFE/NE/INS), SO, SET 2-3/8" TBG AT 4638, NO PKR, POP, P 40 BO & 8  
 BWP, 7/25/95, COMMINGLED