

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20335-00-00
Spot: NWSE Sec/Twnshp/Rge: 31-5S-36W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: BRINEY B Well Number: 1
County: RAWLINS Total Vertical Depth: 4945 feet

Operator License No.: 6509
Op Name: CLARK, JIM D. DBA CLA-MAR OIL, CO
Address: PO BOX 1197
HAYS, KS 67601

Production Casing Size: 4.5 feet: 4762 w/150 sxs cmt
Surface Casing Size: 8.625 feet: 400 w/250 sxs cmt

#16071

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/23/2003 9:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JIM CLARK Company: CLA-MAR OIL COMPANY Phone: (785) 625-3863

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Top down plug.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/23/2003 12:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforations 4465' - 4694'. TD 4945'. PBTD 4762'. Junk in hole at 4100'.
8 5/8" surface casing set at 400' w/250 sxs cement.
4 1/2" production casing set at 4762' w/150 sxs cement.
Connected to 4 1/2" production casing - pumped 250 sxs cement with 500# hulls.
Max. P.S.I. 600#. S.I.P. 250#.
Connected to 8 5/8" surface casing - pumped 50 sxs cement.
Max. P.S.I. 250#. S.I.P. 50#.

RECEIVED
OCT 02 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED

DATE 10-2-03
INV. NO. 2004060563

Form CP-2/3

SEP 24 2003

THUNDERBIRD DRLG., INC.
 P.O. BOX 18407
 WICHITA, KS. 67218

#1 BRINEY "B"

31-5-36W
 C NW SE

CONTR CO. TOOLS _____ CTY RAWLINS _____

GEOL _____ FIELD TOVREA CONF _____

E 3417 KB CM 10/15/78^{CARD} ISSUED 12/7/78 IP P 120 BOPD

MARM 4668-72

+	+	+
+	.	+
+	+	+

API 15-153-20,335

SMP	TOPS	DEPTH	DATUM
ANH	3098	+ 319	
B ANH	3146	+ 271	
HEEB	4223	- 806	
TOR	4258	- 841	
LANS	4276	- 859	
B KG	4564	-1147	
MARM	4578	-1161	
PAW	4667	-1250	
CHER	4716	-1299	
MISS	4728	-1311	
RTD	4945	-1528	

8-5/8" 400/250 sx, 4 1/2" 4762/150 sx
 DST (1) 4310-65/45-45-45-45, 600' MW,
 SIP 1324-1315#, FP 87-303#
 DST (2) 4600-25/45-45-45-45, GTS 5",
 TSTM, REC 3090' CL GSY 0, 240'
 SMGO, SIP 1375-1384#, FP 441-1280#
 DST (3) 4647-90/45-45-45-45, GTS 30",
 TSTM, REC 2640' CL GSY 0, 120"
 MGO, SIP 1064-1073#, FP 346-1038#
 DST (4) 4837-80/45-45, 2280' MW W/TR
 0, SIP 1134#, NO FSIP, FP 169#, NO
 FFP

MIGT - CO, PF (MARM) 4668-72, SWB 40
 BO/1 HR, NAT, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

10000