

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20325-00-00
Spot: S2N2NE Sec/Twnshp/Rge: 4-5S-37W
4290 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: BRINEY FARMS Well Number: 2
County: CHEYENNE Total Vertical Depth: 4780 feet

Operator License No.: 32081
Op Name: SMOKEY VALLEY RESOURCES, INC.
Address: 212 E. SUNDERLAND - PO BOX 199
CHASE, KS 67521

Conductor Pipe: Size feet: 315.64
Surface Casing: Size 8.625 feet: 340 w/250 sxs cmt
Production: Size 4.5 feet: 4761 w/250 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/17/2002 1:00 PM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: RANDY Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Order 460 cu.ft. cement slurry.
Plugging Order one permanent plug.
Method: Order 4 sxs common cement.

Plugging Proposal Received By: CARL GOODROW

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 01/17/2002 4:00 PM

KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 340' w/250 sxs cwc. 4 1/2" set at 4761' w/250 sxs.
Prod. Perfs at 4620' - 4626'. Set permanent plug at 4590' with 4 sxs common cement on plug with bailer.
Exempt area - low fluid level - depleted zone.
Shot off and recovered 2000' of casing.
Filled hole with 460 cu.ft. cement slurry.
Plug complete.

Remarks:

Plugged through: CSG

RECEIVED
MAR 12 2002
KCC WICHITA

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE March 13-02

INV. NO. 2002061518

MAR 07 2002

STATE: KANSAS COUNTY: CHEYENNE 4-5S-37W
FIELD: PIANALTO SOUTH S2 N2 NE
OPER: RAYMOND OIL 1140#FNL 1320 FEL SEC
WELL: 2 BRINEY FARMS WELL CLASS: DO ELEV: 3379 KB
API: 15-023-20325 STATUS: OIL 3374 GR
SPUD: 05/24/93 COMP: 06/07/93
DTD: 4780 LTD: 4780 FTD: CHEROKEE PBD:

LOC: 7 MI SSE BIRD CITY, KS

IP: COMP 6/7/93, IPP 63 BOPD PROD ZONE- PAWNEE 4620-4626
NO CORES, THREE DSTS

LOG TOPS:

STONE CORRAL	3093 286	MUNCIE CREEK	4357 -978
B/ STONE CORRAL	3130 249	STARK	4434 -1055
WABAUNSEE	3908 -529	PAWNEE	4618 -1239
HEEBNER	4184 -805	CHEROKEE L	4702 -1323
LANSING	4238 -859		
TD	4780 -1401		

LOG TYPES: GRDL;

CSGS: 8 5/8 @ 340 W/250 SX, 4 1/2 @ 4761 W/250 SX; TBG: 2 @ 4683; DRLG COMP
06/01/93 RIG REL 06/02/93

STATE: KANSAS COUNTY: CHEYENNE 4-5S-37W
FIELD: PIANALTO SOUTH S2 N2 NE
OPER: RAYMOND OIL 1140 FNL 1320 FEL SEC
WELL: 2 BRINEY FARMS WELL CLASS: DO
(CONTINUED)

DSTS: DST # 1 (TORONTO) 4187-4230, OP 30 MIN, SI 30 MIN, OP 30 MIN, SI 30 MIN, REC:
10 FT MUD, IFP 21, FFP 21, IFP 21, FFP 21, ISIP 976, FSIP 827, BHT 114 DST # 2
(LANSING-KANSAS CITY) 4302-4347, OP 30 MIN, SI 30 MIN, OP 30 MIN, SI 30 MIN,
REC: 8 FT MUD, IFP 32, FFP 32, IFP 32, FFP 32, ISIP 1061, FSIP 1050, BHT 115 DST
3 (PAWNEE) 4604-4630, OP 30 MIN, SI 1 HR, OP 45 MIN, SI 1 HR, 15 MIN, REC:
992 FT GAS, 501 FT GCO, 186 FT SMC GO, IFP 129, FFP 178, IFP 216, FFP 259, ISIP
286, FSIP 286, BHT 113;

PRODUCING INTERVAL: PERF (PAWNEE) 4620-4626 W/2 PF, ACID W/500 GALS, 15%
NE AIR 3 BPM, ATP 1100, ;

OPER ADD: BOX 48788, WICHITA, KS, 67201 PHONE (316) 267-4214;
CONTR: MURFIN DRLG RIG # 2
WELL ID CHANGES: ELEV CHGD FROM 3370 GR;