

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20322-00-00
Spot: SWSENE Sec/Twnshp/Rge: 4-5S-37W
2970 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: BRINEY FARMS Well Number: 1
County: CHEYENNE Total Vertical Depth: 4932 feet

Operator License No.: 32081
Op Name: SMOKEY VALLEY RESOURCES, INC.
Address: 212 E. SUNDERLAND - PO BOX 199
CHASE, KS 67521

Conductor Pipe: Size feet: 8 1/60.29
Surface Casing: Size 8.625 feet: 341
Production: Size 4.5 feet: 4924 w/375 sx cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/27/2002 9:00 AM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: RANDY Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Order 460 cu.ft. cement slurry.
Plugging Order permanent plug.
Method: Order 4 sxs common cement.

Plugging Proposal Received By: CARL GOODROW

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 01/17/2002 11:00 AM

KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 341' cwc. 4 1/2" set at 4924' w/375 sxs.
Prod.Perfs 4594' - 4598'.
Exempt area - low fluid level depleted zone. Fluid level at 900' off bottom.
Set permanent plug at 4540' with 4 sxs common cement on plug with bailer.
Shot off and recovered 2000' of casing.
Filled hole with 460 cu.ft. cement slurry.
Plug complete.

RECEIVED
MAR 12 2002
KCC WICHITA

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

100

INVOICED

Form CP-2/3

DATE March 13-02

INV. NO. 2002061518

MAR 07 2002

STATE: KANSAS COUNTY: CHEYENNE 4-5S-37W
FIELD: PIANALTO SOUTH SW SE NE
OPER: RAYMOND OIL 2000 FNL 690 FEL SEC
WELL: 1 BIRNEY FARMS WELL CLASS: WOE ELEV: 3348 KB
API: 15-023-20322 STATUS: OIL 3343 GR
SPUD: 01/04/93 COMP: 03/24/93
DTD: 4930 LTD: 4932 FTD: MISSISSIPPIAN PBTB:

LOC: 7 1/8 MI SE BIRD CITY, KS

IP: COMP 3/24/93, IPP 160 BOPD, NO WTR PROD ZONE- PAWNEE 4594-4598
NO CORES, THREE DSTS (PAWNEE EXTENSION)

LOG TOPS:

STONE CORRAL	3061 287	STARK	4405 -1057
B/ STONE CORRAL	3097 251	PAWNEE	4591 -1243
HEEBNER	4157 -809	CHEROKEE L	4673 -1325
LANSING	4208 -860	MISSISSIPPIAN	4887 -1539
TD	4932 -1584		

LOG TYPES: CBND, GRNL;

CSGS: 8 5/8 @ 341 CMT, 4 1/2 @ 4924 W/375 SX; TBG: 2 @ 4875; DRLG COMP 01/14/93
RIG REL 01/14/93

DSTS: DST # 1 (HEEBNER TORONTO) 4159-4206, OP 30 MIN, SI 45 MIN,

STATE: KANSAS COUNTY: CHEYENNE 4-5S-37W
FIELD: PIANALTO SOUTH SW SE NE
OPER: RAYMOND OIL 2000 FNL 690 FEL SEC
WELL: 1 BIRNEY FARMS WELL CLASS: WOE
(CONTINUED)

OP 30 MIN, SI 45 MIN, REC: 20 FT MUD, IFP 30, FFP 66, IFP 30, FFP 77, ISIP 1171, FSIP 1105,
BHT 111 DST # 2 (TORONTO LANSING-KANSAS CITY) 4197-4319, OP 30 MIN, SI 45 MIN, OP
45 MIN, SI 45 MIN, REC: 67 FT OCM, 125 FT O&WCM, 410 FT O&MCW, IFP 55, FFP 143, IFP
165, FFP 265, ISIP 1237, FSIP 1171, BHT 112 DST # 3 (LANSING-KANSAS CITY PAWNEE)
4579-4606, OP 30 MIN, SI 1 HR, OP 45 MIN, SI 1 HR, 15 MIN, GAS TS 1 HR NOT RPTD REC:
3413 FT GCO, IFP 729, FFP 1010, IFP 1110, FFP 1210, ISIP 1260, FSIP 1270, BHT 148;
PERFS: PERF (PAWNEE) 4594-4598 W/2 PF, ACID W/500 GALS, 15% NE AIR 3 BPM,
FBRKP 1200, SWBD 43 BOPH NW 900 FT OFF BTM
PRODUCING INTERVAL: PERF (PAWNEE) 4594-4598,

OPER ADD: BOX 48788, WICHITA, KS, 67201 PHONE (316) 267-4214;
CONTR: MURFIN DRLG
GEOL: CLARKE SANDBERG