

4-032096

9-28

API Number: 15-153-20,809-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

S2 SE NW /4 SEC. 29, 05S, 36 W
2970 feet from S section line
3300 feet from E section line

Operator license# 4767 Lease: Ruth Briney Trust Well # 1
Operator: Ritchie Exploration, Inc. County: Rawlins 156.33
Address: 125 N. Market Well total depth 4810 feet
Suite #1000 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 3/8 Inch @ 372 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: White & Ellis License# 5420

Address: Great Bend, Kansas 67530

Company to plug at: Hour: P.M. Day: 27 Month: September Year: 1995

Plugging proposal received from: Judy

Company: White & Ellis Phone: -

Were: Order 190 sxs 60/40 pozmix - 6% gel - 3% c.c.
Allied Cement Company.
Condition hole with at least 36 vis. mud.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 12:00 P.M., Day: 28, Month: September, Year: 1995

Actual plugging report:

Spot cement plugs with drill pipe.

1st. Plug at 3050' w/25 sxs.

2nd. Plug at 2200' w/100 sxs.

3rd. Plug at 425' w/40 sxs.

4th. Plug at 40' w/10 sxs. - W.P.

Circulated 15 sxs in rathole.

RECEIVED
STATE CORPORATION COMMISSION

OCT 11 1995

CONSERVATION DIVISION 10-11-95
Wichita, Kansas

Remarks: Condition of casing(in hole): GOOD BAD Anhy.plug: YES 3061 NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO
Plugged through TUBING, CASING. Elevation: 3357 GL

I did/did not [X] observe the plugging.

Carl Goodrow
(agent)

DATE 10-11-95

INV. NO. 43720

9-28