

010291

15-153-20581-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-153-20581 R

SE, SEC. 1, T. 5 S, R. 36 W

1445 feet from S section line

1450 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8762

Lease Name Minney Well # 2

Operator: Magnus Oil & Gas

County Rawlins 148.85

Name & Address 1002 4th St

Well Total Depth 4580 feet

Arapahoe Nebr.

Conductor Pipe: Size _____ feet

68922

Surface Casing: Size 8 5/8 feet 172

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Golden Eagle License Number 8682

Address Box 983 McCook Nebr.

Company to plug at: Hour: 11:30 AM Day: 10 Month: 2 Year: 19 85

Plugging proposal received from Patric Brenning

(company name) Golden Eagle (phone) _____

were: order 195 sx. cement 50/50 port mix 6% Gyl. 3% cc.

Heavy mud Between all plugs

Pump cem. down drill pipe.

Elev. 3115 Anhydrite 2838-72 Arbuckle No.

Dakota 1325 Plugging Proposal Received by Nalef Balthazor

1790-2090 (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None (3)

Operations Completed: Hour: 10 PM Day: 10 Month: 2 Year: 19 85

ACTUAL PLUGGING REPORT circ @ 2850 for 30 mi.

25 SX @ 2850

100 SX @ 2090

40 SX @ 200

10 SX @ 40 on Solid Bridge

10 SX Rot Hole

Remarks: 10 SX Mouse Hole cem to Sun

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 2-25-85

Signed Nalef Balthazor 16 85
(TECHNICIAN) 2-15

INV. NO. 7083 MAR 15 1985

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1985
2-15-85
CONSERVATION DIVISION
Wichita, Kansas