

4-031880

7-5

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-153-20,797-00-00

C NW SE /4 SEC. 32, 05 S, 36 W  
1980 feet from S section line  
1980 feet from E section line

Operator license# 5046 Lease Briney A well # 1

Operator: Raymond Oil Company, Inc. County Rawlins

Address: P.O. Box 48788 Well total depth 4720 feet  
Wichita, Kansas 67201 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 388 feet

153.40

Aband. oil well \_\_, Gas well \_\_, Input well \_\_, SWD \_\_, D & A X

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: Wichita, Kansas 67201

Company to plug at: Hour: P.M. Day: 5 Month: July Year: 93

Plugging proposal received from: Ed McKenna

Company: Murfin Drilling Company, Inc. Phone: \_\_\_\_\_

Were: Order 215 sxs. 60/40 pozmix - 6% gel - 3% cc.  
Allied Cement Company.  
Circulate and condition hole.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 2:00P.M., Day: 5, Month: July, Year: 1993

Actual plugging report: Spot cement plugs with drill pipe.  
1st. plug at 3150' w/50 sxs.  
2nd. plug at 2125' w/100 sxs.  
3rd. plug at 400' w/40 sxs.  
4th. plug at 40' w/10 sxs.  
15 sxs. in rathole.

Remarks: Anhy. 3150'  
Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy. plug: YES X NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO X Dakota plug: YES X, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_. Elevation: 3372 GL

RECEIVED

STATE CORPORATION COMMISSION

I did not observe the plugging.

Carl Goodrow

DEC 10 1993

**INVOICED**  
DATE 12-10-93  
INV. NO. 39460

(agent) CONSERVATION DIVISION  
Wichita, Kansas  
Form CP-2/3 12-10-93