

4-031958

7-7

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-153-20,800-00 -00
30' N. of
C SW SE /4 SEC. 31, 05 S, 36 W
690 feet from S section line
1980 feet from E section line

Operator license# 6600 Lease Briney well # 5

Operator: Don Karst Well Servicing County Rawlins

Address: P.O. Box 1316 Well total depth 4760 feet *154.70*
Hays, Kansas 67601
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 407 feet

Aband. oil well __, Gas well __, Input well __, SWD __, D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 28 Month: July Year: 94

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone: _____

Were: Order 190 sxs. 60/40 pozmix - 6% gel - 3% c.c.
Allied Cement Company. Circulation was lost @ 2986' - much LCM was
used with cement across cedar hill interval. The rig drilled out over
400' of cement plug across. C.H. lost circulation area.
Condition hole with 36+ vis. mud.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 5:00P.M., Day: 7, Month: July, Year: 94

Actual plugging report: Spot plug with drill pipe.
1st. plug @ 3050' w/25 sxs.
2nd. plug @ 2220' w/100 sxs.
3rd. plug @ 450' w/40 sxs.
4th. plug @ 40' w/10 sxs.
10 sxs. in mousehole.
15 sxs. in rathole.

STATE CORPORATION COMMISSION

AUG 12 1994

8-12-94

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks:
Condition of casing (in hole): GOOD __ BAD __ Anhy. plug: YES X NO __
Bottom plug (in place): YES __, CALC __, NO X Dakota plug: YES X, NO __
Plugged through TUBING __, CASING __. Elevation: __ GL

I did not [X] observe the plugging. Carl Goodrow

INVOICED
DATE 8-24-94
SER. NO. 40967

HO

(agent)