

6030348

API NUMBER 15-153-20,348-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SESW, SEC. 31, T. 5 S, R. 36 WE

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6978

Lease Name TOVREA Well # B-1

Operator: NIELSON ENTERPRISES INC.

County RAWLINS 16/53

Name & Address 1675 BROADWAY, STE. 2770

Well Total Depth 4970 feet

DENVER, COLORADO

Conductor Pipe: Size _____ feet

80202

Surface Casing: Size 8 5/8 feet 391

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON SERVICES License Number _____

Address OBERLIN KANSAS

Company to plug at: Hour: PM Day: 14 Month: 11 Year: 19 84

Plugging proposal received from GIB SPERLING

(company name) NIELSON ENT. INC. (phone) _____

were: DUMP SAND ON P.B.T.D. WITH 4 SX. COM. CEM. ON TOP BY DUMP BAIER
SHOOT OFF 4 1/2 CASING AND RECOVER PIPE - T.O.S. 4600' PERFS 4665-87
SHOTS AT 3110' ANNY. - 1775' WITH RECOVERY OF 1775' OF 4 1/2" CASING.
ORDER 170 SX. 50/50 PORE GEL 3 ACC 1- 8 5/8 WIPER PLUG FOR TOP PLUG.
CALL BACK WHEN READY FOR TOP PLUG.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:20 PM Day: 14 Month: 11 Year: 19 84

ACTUAL PLUGGING REPORT SAND BOTTOM TO 4600 WITH 4 SX. COM. CEM. ON TOP

TOP PLUG - PUMP DOWN 8 5/8 WITH - 10 SX. GEL + 4 SX. HULLS - 100 SX. CEM. MIX.
40 SX. GEL - 8 5/8 WIPER PLUG - 70 SX. CEM. MIX.

MAX. PRESSURE 300^{PSI} - SHUT IN 150^{PSI} PLUG DOWN AT 1:20 PM 11-14-84

Remarks: _____

(If additional description is necessary, use BACK of this form.)

(did) did not observe this plugging.

INVOICED
DATE 12-12-84
INV. NO. 5915

Signed Carl Goodrow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
DEC 03 1984
12-3-84

11-30-84
9