

3-23
4-031908

15-153-20338-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -

C SW SE /4 SEC. 31, 05 S, 36 W
660 feet from S section line
1980 feet from E section line

Operator license# 6600

Lease Briney "B" well # 2

Operator: Don Karst Well Service, Inc.

County Rawlins

Address: P.O. Box 1316
Hays, Kansas 67601

Well total depth 4680 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 419 feet

152.10

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License#

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 23 Month: March Year: 94

Plugging proposal received from: Don Karst

Company: Don Karst Phone:

Were: Emergency plug. The condition of the 4 1/2" was judged to be too costly to repair so was plugged. Cement was on location with 400 sxs. 60/40 pozmix - 2% gel - ordered gel and hulls to blend in. 4 1/2" casing-ruled out a liner. Production perf's were open - bad pipe was found from 2300' to 3200'. Hole tested to 4400'. Pitted and tight holes. Cleaned out 6.82 - 4683' TD.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:00P.M., Day: 23, Month: March, Year: 94

Actual plugging report: 8 5/8" set at 419' cwc. 4 1/2" set at 4680' with 150 sxs. Prod. perfs 4420' - 4674'. Holes at critical areas 2300' and 3200'. Squeezed 8 5/8" with 100 sxs. - 50# hulls. Max. P.S.I. 400#. Close in P.S.I. 300#. Squeezed 4 1/2" with 300 sxs. cement blend with 450# hulls mixed in to Max. P.S.I. 400#. Close in P.S.I. holding zero P.S.I. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD X Any plug: YES X NO STATE CORPORATION COMMISSION
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 3416 GL

RECEIVED

MAR 28 1994

I did [X] / did not [] observe the plugging.

Carl Goodrow
CONSERVATION DIVISION
Wichita, Kansas

(agent)

Form CP-2/3

INVOICED

DATE 4-6-94

INV. NO. 40223

3-23