

15-153-20330-00-00

R

6
030345

API NUMBER 15-153-20,330

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE, SEC. 31, T. 5 S, R. 36 WE

TECHNICIAN'S PLUGGING REPORT

1980 feet from (S) section line

1980 660 feet from (W) section line

Operator License # 6978

Lease Name TOUREA Well # 1

Operator Name & Address: NIELSON ENTERPRISES INC.
1675 BROADWAY STE. 2770

County RAWLINS 161.53

DENVER COLORADO

Well Total Depth 4970 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 407

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON License Number _____

Address DBERLIN KANSAS

Company to plug at: Hour: PM Day: 16 Month: 11 Year: 19 84

Plugging proposal received from GIB SPERLING

(company name) NIELSON ENT. INC. (phone) _____

were: PLACE SAND ON P.B.T.D. TO 4590 WITH 4 SX. COM. CEM. ON TOP WITH BAILER.
SHOOT 4 1/2 AND RECOVER PIPE

TOP PLUG ORDER 200 SX. 50/50 PZ 6 1/2 GEL 3 1/2 CC - 50 SX. GEL - 4 SX. HULLS.

8 5/8 WIPER PLUG

RECEIVED
STATE CORPORATION COMMISSION
12-3-84

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

DEC 03 1984
CONSERVATION DIVISION
Wichita, Kansas

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:57 Day: 16 Month: 11 Year: 19 84

ACTUAL PLUGGING REPORT BOTTOM SAND BRIDGED AT 600 RIG. DRILLED OUT 220' OF SAND

CLEANED OUT HOLE RESANDS AND PLACED 4 SX. COM CEM. ON SAND SHOT OF PIPE

AND RECOVERED APP. 1800' OF 4 1/2 - TOP PLUG PUMPED DOWN 8 5/8 4 SX. HULLS 10 SX. GEL

100 SX. CEM. MIX. 40 SX. GEL - 8 5/8 WIPER PLUG - 100 SX. CEM MIX.

AFTER THE FIRST 10 SX. GEL + 4 SX. HULLS AND ABOUT 50 SX. CEM. MIX. THE 8 5/8 BLEW

A HOLE WHICH A WELDER REPAIRED AND PLUGGING WAS COMPLETED - 400" MAX - 150" SHUT IN

Remarks: PIPE SHOT AT 3110
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED
DATE 12-12-84

Signed Carl Goodnow
(TECHNICIAN)

INV. NO. 5913