

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

Rev. 12-4-81
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API NUMBER 15-153-20,015-00-00 (of this well)
(This must be listed; if no API# is available, please note drilling completion date.)

LEASE OWNER Mull Drilling Company, Inc.

ADDRESS P. O. Box 2758 @ Wichita, Kansas, 67201 PHONE # (316)-264-6366

LEASE (FARM NAME) Woerpel WELL NO. 1

WELL LOCATION C NE SW SEC. 13 TWP. 5 S RGE. 31 W (East)(West) X

COUNTY Rawlins TOTAL DEPTH 4135' FIELD NAME _____

OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

WELL LOG ATTACHED WITH THIS APPLICATION AS REQUIRED? yes ACO-1 filed? _____
(If not, state reason why)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN immediately

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bob Walls ADDRESS Wichita, Kansas

PHONE # (316)-264-6366

RECEIVED
STATE CORPORATION COMMISSION

JUL 9 1982

7-9-82
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 683

ADDRESS Box 347 Chase, Kansas, 67524 PHONE # (316)-938-2457

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME Mull Drilling Company, Inc.

ADDRESS P.O. Box 2758 @ Wichita, Kansas, 67201 PHONE # (316)-264-6366

AND PAYMENT WILL BE GUARANTEED BY APPLICANT /OR ACTING AGENT.

SIGNED: *R. Daniel Kelso*
Applicant /or Acting Agent

DATE: 7-8-82



JOHN CARLIN
C. LOUX
WANE T. ROY
WILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202

THIS PERMIT

July 12, 1982

OCT 12 1982

EXPIRES

WELL PLUGGING AUTHORITY

Mull Drilling Company, Inc.
P. O. Box 2758
Wichita, KS 67201

Well No.	1
Lease	Woerpel (15-150-20,015)
Description	C NE SW
Section	13-5S-31W
County	Rawlins
Total Depth	4135'
Plugging Contractor	Kelso Casing Pulling

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,


DELBERT J. COSTA Administrator

Mr. Carl Goodrow, Box 189 Penokee Ks. 67659 (913)674-5593
is hereby assigned to supervise the plugging of the above named well.


KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COPY

COMPANY MULL DRILLING, INC. 15-153-2005-0000 REC. 13 T. 5 R. 31W
 FARM Woerpel NO. 1 LOO. C NE SW

TOTAL DEPTH 4135
 COMM. 2-4-68 COMP. 2-14-68
 SHOT OR TREATED
 CONTRACTOR Abercrombie Drlg.
 ISSUED 4-20-68

COUNTY Rawlins
 KANSAS



RECEIVED
 STATE CORPORATION COMMISSION
 7-9-82
 JUL 9 1982
 CONSERVATION DIVISION
 Wichita, Kansas

CASING
 20 10
 15 8" @ 197' w/110 SX
 12 6
 13 4 1/2" @ 4134' w/125 SX

ELEVATION 2871KB

PRODUCTION 135 BOPD,
 LKC 3969-76, GRAV 35

FIGURES INDICATE BOTTOM OF FORMATIONS

0	131	Clay, Rock & Sand
131	230	Shale
230	1040	Shale & Shells
1040	1777	Shale w/Sand Streaks
1777	2090	Shale & Sand
2090	2220	Shale
2220	2250	Gyp
2250	2362	Shale & Gyp
2362	2398	Sand
2398	2578	Red Bed & Shale
2578	2616	Anhydrite
2616	2865	Shale
2865	3021	Shale & Lime
3021	3200	Lime & Shale
3200	3304	Shale & Lime
3304	3767	Lime & Shale
3767	3800	Lime
3800	3900	Lime & Shale
3900	4135	Lime
	4135	Rotary Total Depth

Drilled 200' of 9" hole and set 7" casing @197' w/110 sx. HA-5 cement. Plug was down 10:00 p.m., February 4, 1968.
 4 1/2" production casing was set @4134.1 w/125 sx. 60-40 posmix salt-saturated cement. Plug was down 2:00 p.m., February 14, 1968.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

K. G. S. LIBRARY

A. L. Abercrombie, Abercrombie Drilling, Inc., does hereby certify that the above and foregoing is a true and correct log of the #1 WOERPEL, located in the C NE SW, Section 13-58-31W, Rawlins County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

A. L. Abercrombie
 A. L. Abercrombie

COBS: SCOUT
 Heebner 3850
 Toronto 3883
 Lansing 3901
 Base Kansas City 4119