

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COM.

JUN - 2 1979

7-2-79

CONSERVATION DIVISION
WICHITA, KANSAS

API Number 15 - 137 - 20141-00-00 (of this well)

Lease Owner R. P. Nixon Operations

Address 207 West Twelfth Street Hays, Kansas, 67601

Lease (Farm Name) Schuck Well No. 1

Well Location SE SW SE Sec. 2 Twp. 5 S Rge. (E) 22 W (W)

County Norton Total Depth 3499' Field Name

Oil Well Gas Well Input Well SWD Well Rotary D & A

Well Log attached with this application as required yes

Date and hour plugging is desired to begin immediately

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

R. P. Nixon Address Hays, Kansas, 67601

Plugging Contractor Kelso Casing Pulling License No. 683

Address Box 176 Chase, Kansas, 67524

Invoice covering assessment for plugging this well should be sent to:

Name R. P. Nixon Operations

Address 207 West Twelfth Street Hays, Kansas, 67601

and payment will be guaranteed by applicant or acting agent.

Signed: 
Applicant or Acting Agent

Date: 6 - 29 - 79

State of Kansas



15-137-20141-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202
Telephone (316) 263-3238

July 2, 1979

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Schuck
Description	SE SW SE Sec. 2-55-22W
County	Norton
Total Depth	3499'
Plugging Contractor	Kelso Casing Pulling


R. P. Nixon Operations
207 West Twelfth Street
Hays, Kansas 67601

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

~~Mr. Gilbert Balthazor, P.O. Box 9, Palco, Kansas 67657~~
is hereby assigned to supervise the plugging of the above named well.

CONTRACTOR'S WELL LOG

15-137-20141-00-00

OPERATOR: R. P. Nixon Operations
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Schuck #1
 LOCATION: SE SW SE, Section 2-5S-22W
 Norton County, Kansas
 SPUD DATE: April 27, 1979
 COMPLETION DATE: May 03, 1979

0	265	Sand and shale
265	295	Shale
295	950	Sand and shale
950	1684	Shale and sand
1684	1713	Anhydrite
1713	2435	Shale
2435	2605	Shale and lime
2605	2805	Shale
2805	3210	Shale and lime
3210	3494	Lime and shale
3494	3499	Sand
	3499	Rotary Total Depth

Spud hole at 2:30 p.m., April 27, 1979. Drilled 265' of 12 1/4" hole. Ran 6 joints of 8-5/8" - 28# casing. Set at 263' K.B. with 210 sacks of commo cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 7:30 p.m., April 27, 1979.

T.D. 3499'. Ran 92 joints of 4 1/2" - 9 1/2# casing. Set at 3489' R.T.D. Ran 15 bbls. salt flush, 100 sacks of common cement. Plug was down at 7:00 a.m., May 03, 1979.

SAMPLE TOPS:

Anhydrite 1684'
 B/Anhydrite 1713'

RECEIVED
 STATE GEOLOGICAL COMMISSION

JUL - 2 1979

7-2-79

CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Schuck #1, SE SW SE, Section 2-5S-22W, Norton Count Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 8th day of May, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.