

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number ~~15-153-20,422~~
15-023-20177-00-00

Operator's Full Name NIELSON ENTERPRISES, INC.

Complete Address 1675 BROADWAY ST. 2770 DENVER, COLORADO. 80202

Lease Name BRINEY Well No. # 1

Location C-NE-NW Sec. 4 Twp. 5^S Rge. 37^W (East) (West)

County CHEYENNE Total Depth 4790^{FL} 4970

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor RAINS & WILLIAMSON DRILLING, INC.

Address 435 PAGE COURT
220 WEST DOUGLAS, WICHITA, MO License No. _____

Operation Completed: Hour: 7:45^{PM} Day: 29th Month: JUNE Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8" - 370' EL SP. CUM W/ 250ST 60/40 FOMIX - 2% GEL - 3% CA-CL
ORDERED 105ST 50/50 FOMIX 6% GEL - 8 5/8" PLUG.

SPOTTED WITH DRILL SLURRY - WITH HEAVY MUD BETWEEN ALL PLUGS.

1ST PLUG. @ 1980' EL W/ 60ST CMT.

2ND PLUG. @ 390' FL W/ 30ST CMT.

3RD PLUG. SOLID BRIDGE HALL'S PLUG. @ 410' EL W/ 10ST CMT.

5TH IN RAT HOLE

CEMENTED BY HALL'S DRILLING CO.

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

JUL - 2 1981

INVOICED

Signed: Martin Schmidt
Conservation Division Agent, Kansas

DATE 7-27-81

INV. NO. 6083-W