

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-20164-00-00

Operator's Full Name Murfin Drilling Company,  
 Complete Address 617 Union Center Building, Wichita, Kansas.  
 Lease Name Bell-Wessel Well No. 1  
 Location CNW-NE Sec. 26 Twp. 5 Rge. (E) (W) 30  
 County Decatur Total Depth 3700'  
 Abandoned Oil Well          Gas Well          Input Well          SWD Well          D & A X  
 Other well as hereafter indicated           
 Plugging Contractor Above  
 Address          License No.           
 Operation Completed: Hour 3:15 Am Day 3 Month 7 Year 1970

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1475'.

Circulated hole with heavy mud. Pulled DP to 1700' and displaced 100 Sx. cement thru  
DP from 1700' to 1375'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from  
215 to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 6 1970

I hereby certify that the above well was plugged as herein stated.  
Wichita, Kansas

INVOICED

DATE 7/6/70

INV. NO. 2163-4

07-06-1970

Signed: A. L. Nichols  
Well Plugging Supervisor