

KANSAS



CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1968
08-15-1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-029-20056-00-00

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address: Box #797, Great Bend, Kansas.

Lease Name Wessell Well No. 1

Location NE-NW Sec. 25 Twp. 5 Rge. (E) (W) 30

County Decatur Total Depth 3684

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 2:15 AM Day 11 Month 8 Year 1968

The Above well was plugged as follows:

230'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Top of Dakota section @ 1435'.

Circulated hole with heavy mud. Pulled DP to 1660' and displaced 200 Sx. cement thru
DP from 1660' to 1340'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated

INVOICED

DATE 8/15/68
INV. NO. 8287-4

Signed: M. L. Nichols
Well Plugging Supervisor