



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-039-20164-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Sixbury of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Bell-Wessel Well No. 1

Location: CNW-NE Sec. 26 Twp. 5 Rge. (E)(W) 30

County: Decatur Total Depth 3700' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

208'---8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1475'.

Circulate hole with heavy mud. Pull DP to 1700' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
Very truly yours,

JUL 6 1970

CONSERVATION DIVISION  
Wichita, Kansas

M. L. Nichols  
Conservation Division Agent

07-06-1970