

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-023-20104-00-00

LEASE NAME McKee

WELL NUMBER #1

3,300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 36 TWP. 5S RGE. 37 (E) or (W)

COUNTY Cheyenne

Date Well Completed 7/3/79

Plugging Commenced 11/19/87

Plugging Completed 11/21/87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Nielson Enterprises Inc.

P. O. Box 370

ADDRESS 1825 Big Horn Ave., Cody, WY 82414

PHONE# (307) 587-4291 OPERATORS LICENSE NO. 6978

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 20, 1987 (verbal) (date)

by Carl Goodrow, District #4, Hays, Kansas (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? Yes

Producing Formation Pawnee Depth to Top 4,670 Bottom 4,737 T.D. 4,969

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	404	-0-
				4-1/2	4,969	1,000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
250 ga. sand -- 4,969' to 4,620' -- 4 sks cement -- 4,620' to 4,575'. 4-1/2" casing shot @ 2,200' 1,850' 1,500' 1,000' - pulled 1,000' 4-1/2 csg. How; plugged down 8-5/8" casing w/200 sks Econolite w/5 sks cottonseed hulls in first 50 bbls late pumping pressure 400 psi. S.I. press 200 psi. 11:00 a.m. - 11/21/87.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Flint Engineering Co. License No. 004025 STATE OF NEBRASKA COMMISSION

Address Box 669, McCook, Nebraska 69001

STATE OF Wyoming COUNTY OF Park, ss.


Robert L. Snyder (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert L. Snyder

Vice President, Finance

(Address) P. O. Box 370, Cody, WY 82414



SUBSCRIBED AND SWORN TO before me this 30th day of November, 1987

Shirley A. Fenimore
 Notary Public

My Commission Expires: Oct 15, 1988

RECEIVED
 DEC 3 1987
 12-3-87
 CONSERVATION DIVISION
 Wichita, Kansas