

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-023-20,172-00-00

LEASE NAME Fisher

WELL NUMBER 5

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 35 TWP. 5 RGE. 37W (E) or (W)

COUNTY Cheyenne

Date Well Completed

Plugging Commenced 2-17-94

Plugging Completed 2-22-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS Rt. 1 Box 56 Great Bend, KS 67530

PHONE#(316) 793-8186 OPERATORS LICENSE NO. 5393

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filled? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 5025'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	367'	none
				4 1/2	4447'	1815'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom @ 4550' & 5 sks cement. Shot @ 2919, 2120, worked pipe. Mixed 125 sks w/200# hulls & displaced to 1850 w/100# psi. Shot @ 1815, pulled 5 jts, mixed 88 sks w/300# hulls w/200# psi. Pulled to 350, pumped rest of cement, did not circulate. Pulled rest of pipe. 65/35 pos 10% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) R. Darrell Kelso **MAR 02 1994**

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 28th day of February, 19 94

Irene Herzberg
Notary Public

My Commission Expires:

