

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9/22/04 (Date)
by: Jeff Klock (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Chert Depth to Top: 3674 Bottom: 3682 T.D. 3722
Mississippi Dolomite Depth to Top: 3716 Bottom: 3722 T.D. 3722
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-173-20,570-00-00
Lease Name: Lentz
Well Number: 1
Spot Location (QQQQ): NE SW - App - 8/2 - SW - NW
440' 2230' Feet from North / South Section Line
600" Feet from East / West Section Line
Sec. 20 Twp. 27S S. R. 04W East West
County: Sedgwick
Date Well Completed: 6/14/83
Plugging Commenced: 9/28/04
Plugging Completed: 9/28/04

KCC
BEM
1-20-05
RBDMS
CP 2/3
CP-1

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi	sli oil, gas, sw	3674	3722	8-5/8"	267'	none
				5-1/2"	3716'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tubing open ended at 3707', United spotted 75 sx Clas A, 3% cc plug. Pull tubing out. Wireline tag cement at 3058'.
Loadhole, bond log 800' to 0'. Cement above salt section, but not below. Perfs at 690'. Tubing in hole to 690'.
Mix and spot 50 sx Class A, 2% cc, squeeze out some. Pull out. Wireline tag at 500' (27 sx out, 23 sx in csg). Tubing to 310'.
Circulate full with 56 sx Class A. Pull out top off with 14 sx. United Ticket #5733.

Name of Plugging Contractor: North Fork Well Service, LLC License #: 32938
Address: 7 SW 26th Avenue, Great Bend, KS 67530

Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss.


W. R. Horigan (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 30th day of September

Michelle D. Henning
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT 01 2004
KCC WICHITA

[Handwritten mark]



United Cementing and Acid Co., Inc.

SERVICE TICKET

5733

Oil Well Cementing & Acidizing
 (316) 321-4680 • 800-794-0187 • FAX (316) 321-4720
 2510 West 6th Street • El Dorado, KS 67042

DATE 9-28-04

COUNTY Sedgwick CITY _____

CHARGE TO Vess Oil Corp.
 ADDRESS _____ CITY _____ ST _____ ZIP _____
 LEASE & WELL NO. Lentz CONTRACTOR North Fork Well Serv.
 KIND OF JOB Old hole plug SEC. _____ TWP. _____ RNG. _____
 DIR. TO LOC. Cheney Lake Exit 3/4 N, E Into. 7:45 OLD NEW

Quantity	MATERIAL USED	Serv. Charge
1955x	class A	
25x	calcium Chloride	
1975x	BULK CHARGE	
85	BULK TRK. MILES	
85	PUMP TRK. MILES	
	PLUGS	
		SALES TAX
		TOTAL

T.D. 3715 ft. **RECEIVED**
 SIZE HOLE _____
 MAX. PRESS. _____
 PLUG DEPTH _____
 PLUG USED _____

CSG. SET AT _____ VOLUME _____
 TBG SET AT _____ VOLUME _____
 SIZE PIPE 5 1/2" casing
 PKER DEPTH _____
 TIME FINISHED 4:30

REMARKS: Ran 2 3/4" tubing to 3707 ft. Brake circulation, Mix & pump 755x class A 3% CC & disp. Pulled tubing out. Ran wire line to 3058 ft. & taged cement. Ran bond log, then shot holes at 690 ft. & Ran tubing to 690 ft. Brake circulation, Mix & pump 505x class A 3% CC & disp. Pulled tubing out. Ran wireline to cement at 500 ft. Ran tubing to 310 ft. Brake circulation, Mix & Pump 705x class A to surface cement circulated in cellar.

EQUIPMENT USED
 NAME UNIT NO. NAME UNIT NO.
Chet Johnson P-14
James R. Thomas 26
 CEMENTER OR TREATER

OWNER'S REP.
Josh Greely, Jerry Hudson, B-3, B-1