

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior Inc.
Address: P.O. box 399 Garden City Kansas 67846
Phone: (620) 275-2963 Operator License #: 4058
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 1/13/05 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3233' Bottom: 3241' T.D. 3241'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-159-01982-00-00
Lease Name: Volkland
Well Number: #2
Spot Location (QQQQ): C - NW - SE - SW
990' Feet from North / South Section Line
3630 Feet from East / West Section Line
Sec. 32 Twp. 18 S. R. 9 East West
County: Rice
Date Well Completed: 7/2/48
Plugging Commenced: 1/13/05
Plugging Completed: 1/14/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Oil	Surface	313'	85/8	313	0
		Surface	3233'	51/2	3233'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf: 1100',900',365'. Ran tbg to 3214',Pumped 50sxw/700# Hulls,Pulled tbg to 1100',Pumped 35sx plug, Pulled to 900',
Pumped 35sx plug, Pulled to 365',Pumped 120sx cement. 1/14/05. Tagged cement at 2362'. Pulled tbg to 1100',pumped 35sx plug, Pulled to 900',pumped 35sx plug, pulled to 365',Cir to surface w/55sx. 60/40 pos w/ 2%gel.
Hooked up to surface pipe. pumped 40sx.

Name of Plugging Contractor: Swift Services Inc. Express Well Service License #: 6426 32382
Address: P.O. Box 466 Ness City Ks. 67560
Name of Party Responsible for Plugging Fees: American Warrior Inc.
State of Kansas County, Finney, ss.

RECEIVED
JAN 20 2005
KCC WICHITA
KCC
ccm
1/21/05
RBomv5
CP 2/3

Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jody Smith
(Address) P.O. Box 399 Garden City Ks. 67846

SUBSCRIBED and SWORN TO before me this 15 day of January
Mary L. Watts My Commission Expires _____
Notary Public



Bm