

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior Inc.
Address: P.O. box 399 Garden City Kansas 67846
Phone: (620) 275-2963 Operator License #: 4058
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 1/12/05 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 159-06456 - 00 - 00
Lease Name: Habiger
Well Number: #1
Spot Location (QQQQ): C - NW - NW - NW
330 Feet from North / South Section Line
330' Feet from East / West Section Line
Sec. 5 Twp. 18 S. R. 10 East West
County: Rice
Date Well Completed: 10/1/37
Plugging Commenced: 1/12/05
Plugging Completed: 1/12/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	530'	13"	530'	0
		Surface	2944'	7"	2944'	0
		2624'	3003'	51/2	379'	0
		2980'	3215'	41/2	235'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf: 3210', 1250', 900', 580', 2spf. Ran tbg to 3210', Pumped 10sx plug with 600# hulls, pulled tbg to 1250', Pumped 80sx plug Pulled tbg to 900', Pumped 80sx plug, Pulled tbg to 580', Cir cement to surface with 70sx. Hooked up to surface. pumped 15sx. Pressured to 200#. Topped 7" off with 20sx. Cement was 60/40 Posw/ 2% gel.

Name of Plugging Contractor: Express Well Service Supply License #: 6426 32382
Address: P.O. Box 466 Ness City Ks. 67560
Name of Party Responsible for Plugging Fees: American Warrior Inc.
State of Kansas County, Finney, ss.
Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
(Signature) Jody Smith
(Address) P.O. Box 399 Garden City Ks. 67846

RECEIVED
KCC
BEM
1-21-05
R6DMS
JAN 20 2005
KCC WICHITA

SUBSCRIBED and SWORN TO before me this 15 day of January
Mary L. Watts My Commission Expires _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bu