

15-039-19030-00-01


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Decatur County. Sec. 35 Twp. 5S Rge. 29W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE SW  
Lease Owner THE HENDERSON OIL COMPANY  
Lease Name WACHENDORFER Well No. 1  
Office Address 502 Orpheum Bldg. Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) DRY  
Date well completed February 8th, 1954 19  
Application for plugging filed 19  
Application for plugging approved February 18, 1954. 19  
Plugging commenced February 24th 19 54  
Plugging completed February 27th 19 54  
Reason for abandonment of well or producing formation



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Lansing K.C. Depth to top 3942 Bottom 4146 Total Depth of Well 4192 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	274'	None
				5-1/2"	4190'	1492'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Original total depth was 4192'.  
Lane Wells plug set at 4102' and casing perforated from 4089' to 4094'.  
Filled hole with sand from 4102' to 4070' and ran 4 sacks of cement at 4070'.  
Mudded hole to 200', set a 10' rock bridge and ran 15 sacks of cement at 190'.  
Mudded hole to 35', set a 10' rock bridge and ran 10 sacks of cement on top.  
Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, SS.  
J. A. HENDERSON (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Henderson President  
502 Orpheum Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of March, 1954

Notary Public. J. A. Swanson

My commission expires April 28, 1954.



23-8390-s 6-51-20M

MAR 11 1954  
CONSERVATION DIVISION  
Wichita, Kansas  
3-11-54

WELL LOG

The Henderson Oil Company et al-Owners - Wachendorfer #1  
NE NE SW  
Section 35-5-29W  
Decatur County, Kansas  
D & A

Elevation 2814 R. B.

Tops at Rotary Bushing

Topeka 3742  
Heebner 3897  
Lansing 3942

Figures indicate bottom of formation

0 - 120 Soil and clay  
195 Sand  
460 Shale  
1040 Shale and shells  
1130 Sand  
1915 Shale and sand  
2510 Shale and shells  
2605 Anhydrite  
3410 Shale and shells  
3505 Lime  
4190 Lime and shale  
4190 T. D.  
Old well cleaned out to  
4190

Pipe Record:

8-5/8" set at 274'  
5-1/2" set at 4190'

Commenced: January 24, 1954  
Completed: February 8, 1954

Cable Tool:

Clean out to 4152'  
Perf. 4078-79 and 4105-6  
Squeeze with 460 sks  
Perf. 4115-19; 1000 acid  
.4 bph water  
Perf. 4089-94; 1000 acid  
25 bph water

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

I, J. A. Henderson, President of The Henderson Oil Company, part owner of the above described well, being first duly sworn on oath, declare: That, I have knowledge of the facts, statements, and matters herein contained pertaining to the log of the above described well, and that the same are true and correct.

J. A. Henderson  
J. A. Henderson

Sworn and subscribed to before me this 15th day of February, 1954.

Ina Swanson

My commission expires April 28th, 1954.

3-11-54

**PLUGGING**  
FILE SEC 35 T 5 R 296  
BOOK PAGE 14 LINE 20