

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2070  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.S.R.-82-3-117

API NUMBER 15-065-23,028-0000

LEASE NAME Chalfant "B"

WELL NUMBER 1-4

1,730 Ft. from Section Line

2,300 Ft. from Section Line

SEC. 4 TWP. 8 N. R. 22 W. or (W)

COUNTY Graham

Date Well Completed 1-18-05

Plugging Commenced 1-18-05

Plugging Completed 1-18-05

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Comm. Div.  
office within 30 days.

LEASE OPERATOR Russell Oil, Inc.

ADDRESS PO Box 1469, Plainfield, IL 60544

PHONE#(815) 609-7000 OPERATORS LICENSE NO. 3,293

Character of Well D & A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-18-05 (date)

by Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.O. 3,610'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	238'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Push bridge plug to 1,800', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 1,000', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 285', pump 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mousehole.

Name of Plugging Contractor SHIELDS DRILLING CO. License # RECEIVED

Address Shields Bldg., PO Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Russell Oil, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of ~~XXXXXX~~ or ~~XXXXXX~~)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact  
statements, and matters herein contained and the log of the above-described well as filed in  
the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 25th day of January, 2005

Notary Public  
My Appl. Exp. 5-26-09

My Commission Expires:

Form CP-