

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-02883-0001

LEASE NAME Loveridge

WELL NUMBER 3

330 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 10 TWP. 9S RGE. 21W (E) or (W)

COUNTY Graham

Date Well Completed 11/28/43

Plugging Commenced 12/9/04

Plugging Completed 12/10/04

RECEIVED

JAN 28 2005

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Elysium Energy, L.L.C.

ADDRESS 1625 Broadway, Suite 2000, Denver, CO 80202

PHONE# (303) 389-3610 OPERATORS LICENSE NO. 32754

Character of Well Oil-P&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/9/04 (date)

by Rich Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes-old form If not, is well log attached? _____

Producing Formation Toronto/LKC/Arb Depth to Top 3371' Bottom 3788' T.D. 3788'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Toronto	Oil	3370	3380	10-3/4"	240'	None
LKC	Oil	3385	3602	6"	3702'	None
Arbuckle	Oil					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Set Cmt retainer @ 3230'. Cement w/200 sx Class A & 750 sx 60/40 Poz w/10% gel & 50 sx Class A 3% CCL. squeeze to 1500#.
Spot 160 sx 60/40 Poz on top of retainer. Pump gel spacer and pull tbg to 1660'. Pump 275 sx 60/40 Poz w/10% gel.
Pump 25 sx 60/40 Poz w/10% gel at the surface.
Pump 50 sx 60/40 Poz w/10% gel & 3 sx hulls down the 10-3/4" x 6" annulus.

Name of Plugging Contractor Gaschler Well Service License No. 33137

Address 1717 Haney, Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Elysium Energy, L.L.C.

STATE OF Colorado COUNTY OF Denver, ss.

James Annable (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 1625 Broadway, Suite 2000, Denver, CO 80202

SUBSCRIBED AND SWORN TO before me this 25 day of January, 2005

Mendi [Signature]
Notary Public

Commission Expires: 8/26/06



My Commission Expires 8/26/2006

Bu