

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Kansas Natural Gas Operating, Inc. Address: P.O. Box 815 Sublette, Kansas 67877 Phone: (620) 675-8185 Operator License #: 32787 Type of Well: Gas - Hugoton Docket #: NA The plugging proposal was approved on: January 6, 2005 by: Mr. Jim Holland - KCC Is ACO-1 filed? No If not, is well log attached? No Producing Formation(s): List All (If needed attach another sheet) Herrington Depth to Top: 2650' Bottom: 2658' T.D. Krider Depth to Top: 2682' Bottom: 2698' T.D.

API Number: 15 - 081-19000-00-00 Lease Name: F. McCoy Well Number: #1 Spot Location (QQQQ): NW - NW - NW - SE 2540 Feet from North / South Section Line 2540 Feet from East / West Section Line Sec. 12 Twp. 29 S. R. 33 East West County: Haskell Date Well Completed: August 31, 1952 Plugging Commenced: January 10, 2005 Plugging Completed: January 10, 2005

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Fresh Water and Chase Series.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hook onto 7" casing and bullhead 25 barrels of fresh water and 200# of cottonseed hulls then followed with 30 sacks of 60-40 Pozmix cement and 100# of cottonseed hulls. Then pumped 70 barrels of fresh water spacer to 700' from surface then tailed with 110 sacks of 60-40 Pozmix at 13.5# and hole pressured to 700#. Hook onto annulus and pumped up to 400# and backside was full. Total 140 sacks of 60-40 Pozmix on job. Cut wellhead off 6' below ground level weld cap and date then backfill site.

Name of Plugging Contractor: Halliburton License #: #5287 99997 Address: Liberal, Kansas Name of Party Responsible for Plugging Fees: Kansas Natural Gas Operating, Inc. State of Kansas County, Haskell, ss. Steve M. Lehning @ Kansas Natural Gas Operating, Inc.

RECEIVED JAN 18 2005 KCC WICHITA


(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Steven M. Lehning (Address) P.O. Box 815, Sublette, KS 67877

SUBSCRIBED and SWORN TO before me this 13th day of January, 20 05

Kraig L. Gross Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten signature/initials