

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-095-21938-0000
LEASE NAME Whitmer A
WELL NUMBER #3-10

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1650 Ft. from North Line of Section
1320 Ft. from West Line of Section

LEASE OPERATOR McCoy Petroleum Corporation SPOT LOCATION N/2 S/2 NW
ADDRESS 8080 E. Central, Suite 300 Section 10 Township 30s Range 9w
CITY, STATE, ZIP Wichita, Kansas 67206 County Kingman
PHONE # 316-636-2737 Date Well Completed 01/16/05
Character of Well Dry and Abandoned Date Plugging Commenced 01/16/05
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 01/16/05

The plugging proposal was approved on January 14, 2005 (date)
by Dave Wertz (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 4294

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	180	8-5/8"	216'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged well on 01/16/05 as follows: Heavy mud in hole and between all plugs. Plugged using 120 sx of 60/40 Poz, 4% Gel. Bottom plug at 1400'/35 sx, 2nd plug at 300'/35 sx, top plug at 60'/25 sx cemented to surface, rathole with 15 sx, mousehole 10 sx. Plugging completed at 11:30 am on 01/16/05. Acid Services ticket #9186. Received plugging orders on 01/14/05 at 2:00 pm from Dave Wertz. Sterling will notify KCC of plugging on 01/18/05.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 17th day of January, 2005



[Signature]
(Notary Public)

RECEIVED
JAN 18 2005
KCC WICHITA
Form CP-4

My Commission Expires: 1-28-05

[Signature]

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Whitmer A #3-10

LOCATION: N/2 S/2 NW Section 10 T 30s R 9w
API: 15-095-21938-0000 Kingman County, Kansas

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 01/08/05
COMPLETED: 01/16/05

TOTAL DEPTH: DRILLER 4294 FEET
LOGGER No Log FEET

Ground Elevation: 1664
KB Elevation: 1673

LOG

0 -	1 FEET	Top Soil
1 -	6 FEET	Clay
6 -	20 FEET	Sand and Gravel
20 -	68 FEET	Sandy Clay
68 -	175 FEET	Sand, Gravel and Clay
175 -	1650 FEET	Shales and Salt
1650 -	4294 FEET	Limestone/Shales

CASING RECORDS

Surface Casing:

Spud at 9:15 pm on 01/08/05. Drilled 12-1/4" hole to 235'. Ran 5 joints of new 24# 8-5/8" surface casing tally 219.69' set at 230.69' KB. Cemented with 250 sx 60/40 Poz, 2% Gel, 3% CC, 1/4#/sx Celloflake. Plug down at 4:30 pm on 01/08/05 by Acid Services, ticket #9467. Cement did circulate. Welded straps on bottom 2 jts, of SP, then tacked collars on next 3 joints.

Plugging Data:

Plugged well on 01/16/05 as follows: Heavy mud in hole and between all plugs. Plugged using 120 sx of 60/40 Poz, 4% Gel. Bottom plug at 1400'/35 sx, 2nd plug at 300'/35 sx, top plug at 60'/25 sx cemented to surface, rathole with 15 sx, mousehole 10 sx. Plugging completed at 11:30 am on 01/16/05. Acid Services ticket #9186. Received plugging orders on 01/14/05 at 2:00 pm from Dave Wertz. Sterling will notify KCC of plugging on 01/18/05.

DEVIATION SURVEYS

3/4 degree(s) at 235 feet
1/2 degree(s) at 4284 feet

RECEIVED
JAN 18 2005
KCC WICHITA