

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-159-22447-00.00
LEASE NAME Volkland
WELL NUMBER B-83

*KCC
DEM
1-19-05
RBMS*

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1650 Ft. from South Line of Section
660 Ft. from West Line of Section

LEASE OPERATOR Don Fox SPOT LOCATION C S/2 NW SW
ADDRESS 2700 Westminister Section 27 Township 18s Range 9w
CITY, STATE, ZIP Hutchinson, Kansas 67502 County Rice
PHONE # 620-662-2862 Date Well Completed 01/10/05
Character of Well D & A Date Plugging Commenced 01/10/05
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 01/10/05

The plugging proposal was approved on January 10, 2005 (date)
by Steve VanGieson (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3265

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	180	8-5/8"	216	0
Redbeds	Shale					
Anhydrite						
Redbeds and Shales						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged well on 01/10/05 as follows: Heavy mud in hole and between all plugs. Plugged using 200 sx of 60/40 Poz, 6% Gel in hole. Bottom plug at 3250' with 35 sx, 2nd plug at 1500' with 35 sx, 3rd plug at 700' with 35 sx, 4th plug at 250' with 35 sx, top plug at 60' with 60 sx cemented to surface. Rathole with 15 sx, no mousehole.
Job complete at 2:30 pm on 01/10/05. Allied Cementing ticket #20239. KCC notified of plugging on 01/11/05.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Don Fox (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 17th day of January, 2005



Pamela S. Fields
(Notary Public)

My Commission Expires: 1-28-05

RECEIVED
JAN 18 2005
KCC WICHITA

Form CP-4
Revised 12-92

bm

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Volkland B-5

LOCATION: C S/2 NW SW
API: 15-159-22447-00.00

Section 27 T 18s R 9w
Rice County, Kansas

OWNER: Don Fox
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 04-Jan-05
COMPLETED: 10-Jan-05

TOTAL DEPTH: **DRILLER** 3265 FEET
LOGGER No Log FEET

Ground Elevation: 1710
KB Elevation: 1719

LOG

0 -	4 FEET	Top Sand
4 -	22 FEET	Clay
22 -	87 FEET	Sand, Rock and Shale
87 -	180 FEET	Shales, Sand and Clay
180 -	700 FEET	Redbeds
700 -	373 FEET	Shales
373 -	1180 FEET	Shales and Salt
1180 -	3250 FEET	Limestone, Shale and Dolomite
3250 -	3265 FEET	Arbuckle

CASING RECORDS

Surface Casing-8-5/8"

Spud at 7:30 am on 01/04/05. Drilled 12-1/4" hole to 213'. Ran 5 joints of 8-5/8" surface casing, tally 216' set at 213' KB. Cemented with 165 sx 70/30 Poz; 2% Gel, 3% CC, Plug down at 1:45 pm on 01/04/05 by Allied Cementing. Ticket #20563. Cement did circulate. Strapped bottom 3 joints, welded collars next 2 joints.

Production Casing-5-1/2"

Plugged well on 01/10/05 as follows: Heavy mud in hole and between all plugs. Plugged using 200 sx of 60/40 Poz, 6% Gel in hole. Bottom plug at 3250' with 35 sx, 2nd plug at 1500' with 35 sx, 3rd plug at 700' with 35 sx, 4th plug at 250' with 35 sx, top plug at 60' with 60 sx cemented to surface. Rathole with 15 sx, no mousehole. Job complete at 2:30 pm on 01/10/05. Allied Cementing ticket #20239. KCC notified of plugging on 01/11/05.

DEVIATION SURVEYS

1-1/4	degree(s) at	213	feet
1-1/2	degree(s) at	3265	feet

RECEIVED
JAN 18 2005
KCC WICHITA