


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

DECATUR COUNTY, County. Sec. 19 Twp. 5S Rge. 30W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner K & E DRILLING, INC.
Lease Name ROULIER Well No. 1
Office Address 719 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed December 17, 19 59
Application for plugging filed December 17, 19 59
Application for plugging approved December 17, 19 59
Plugging commenced December 17, 19 59
Plugging completed December 17, 19 59
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4531' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 500' set plug with 20 sx cement. Filled with heavy mud set plug with 20 sx cement and 1/2 sx hulls thru drill pipe. Filled with heavy mud to 40' set solid bridge with 10 sx cement to base fo cellar.
Job complete 12-17-59 .

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1959
12-23-1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
Dale Silcott, of K & E DRILLING, INC.
719 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of December, 19 59

My commission expires August 11th, 1962.
Patricia M. Edwards, Notary Public.



DRILLER'S WELL LOG

OPERATOR: **K & E DRILLING, INC.**
 719 Union Center Building
 Wichita 2, Kansas

WELL NAME: #1 ROULIER
 LOCATION: NW NW NW
 Sec. 19-58-30W
 DECATUR COUNTY
 KANSAS

CONTRACTOR: **K & E DRILLING, INC.**
 719 UNION CENTER BLDG.
 WICHITA, KANSAS

COMMENCED: December 8th, 1959

CASING RECORD: 8-5/8" @ 250' (200 sx cmt)

COMPLETED: December 17th, 1959

ELEVATION: 2950' KB

ROTARY TOTAL DEPTH: 4531'

PRODUCTION: D & A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Cellar & Clay	50
Sand	75
Shale	160
Sand	200
Shale	1530
Sand & Shale	1940
Shale	2150
Sand & Shale	2155
Shale	2200
Red Bed	2300
Anhydrite	2325
Shale & Red Bed	2420
Anhydrite	2440
Shale	2650
Lime & Shale	3135
Lime	3850
Lime & Shale	2950
Lime	4260
Lime & Shale	4365
Shale & Sand	4512
Mississippian	4531
R.T.D.	4531

CERTIFICATION

State of KANSAS }
 County of SEDGWICK } ss:

I, Dale Silcott, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Dale Silcott
 Dale Silcott

Subscribed and sworn to before me this 22nd day of December, 19 59.

Patricia M. Edwards
 Patricia M. Edwards, Notary Public.

My Commission expires: August 11th, 1962.

