

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-039-20,304-00-00

LEASE NAME Huber

WELL NUMBER #1

SPOT LOCATION SE NW

SEC. 21 TWP. 5S RGE. 30W (E) or (W)

COUNTY Decatur

Date Well Completed _____

Plugging Commenced 2-27-86

Plugging Completed 3-6-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A.L. Abercrombie, Inc.

ADDRESS 801 Union Center Wichita, Kansas 67202

PHONE # (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well OT1
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4170'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	228'	none
				4-1/2"	4173'	1626'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped bottom with 4 hulls, 50 cement and wiper plug to 2192'. A hot pipe @2186', 1814', 1626', pulled a total of 44 joints (1626') of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 100 cement w/ 1 hull, 30 gel, released plug and 80 cement, 60/40 pos, 6% gel, 3% cc. Plugging Cement.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso
(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 10th day of March, 1986

My Commission expires:



STATE OF Kansas Notary Public Irene Hoover

MAR 11 1986
03-11-1986
CONSERVATION DIVISION
Wichita, Kansas