

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

#4
 API NUMBER 15-023-20185-00-01

LEASE NAME McKee

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 34-36

660 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 36 TWP. 5S RGE. 37 (E) of (W)

LEASE OPERATOR MAREXCO

COUNTY Chèyenne

ADDRESS P.O. Box 706, Edmond, Oklahoma 73034

PHONE# (405) 340-6387 OPERATORS LICENSE NO. 9152

Date Well Completed 1-28-88

Character of Well D&A

Plugging Commenced 1-28-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-28-88

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation N/A Depth to Top xxxxxxxxxxxx Bottom xxxxxxxxxxxx T.D. 4660

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing J	Water	4480	4484	4 1/2"	4660	2500
Lansing H	Dry	4443	4446			
Lansing B	Water	4338	4342			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CIBP @ 4476 w/ 1sx cem on top, 25sx 60/40poz, 6%gel, 1sk hulls from 4471-4071, mud to 2500, 60sx same cem from 2500 to 2150, mud to 400, 40sx same cem from 400-200, mud to 40', 10sx from 40' to surface. Cut off and capped 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. _____

Address Ness City, Ks

STATE OF Kansas COUNTY OF Seward, ss.

R. F. Burke

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) RFB

(Address) P.O. Box 1162, Liberal, KS 67905-1162

SUBSCRIBED AND SWORN TO before me this 10th day of February, 19 88



Sharon E. Freeman
 Notary Public

My Commission Expires: 01-04-91

Sharon E. Freeman